

**SURVEY & REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

**Nov 16 2 01 PM '94**

For corners in **APR 28 1995**

**NANCY HAVILAND  
 REGISTER OF DEEDS  
 LIVINGSTON COUNTY, MI  
 48843**

LIVINGSTON (County) **COMMISSION** Located In: Corner Code G-12

1. Public Land Survey T 1N R 4E \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 In Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

L.S.C.#350m  
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**PUTNAM TWP.**

I, DARRELL HUGHES, in a field survey on NOVEMBER 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1823 Joseph Wampler, Deputy Surveyor  
 Black Oak 16" South 69 degrees West 216 links  
 No other bearing tree

\*Additional historical information on back of sheet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 3/4" iron pipe at East, West and South fence intersection in swamp

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


G-12, T1N, R4E, PUTNAM, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.  
 135 DEG. 18.90' SET NAIL/TAG SW/S 11" ELM.  
 185 DEG. 19.66' SET NAIL/TAG E/S 7" ELM.  
 268 DEG. 60.48' SET NAIL/TAG N/S 36" ELM.  
 180 DEG. 1.05' SET NAIL/TAG E/S WOOD FENCE POST.

Signed by Darrell Hughes Date 11-8-94

Surveyor's Michigan License No. 19834

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY  
 PEER GROUP ON 28 Sep 94 CO. REP [Signature]



PUTNAM TOWNSHIP, T1N, R4E

G-12, COMMON 1/4 CORNER FOR SECTIONS 33 AND 34

FIELD: 12 SEPT 1994

FOUND 3/4" IRON PIPE 6.4' LONG AT AN EAST, WEST, AND SOUTH FENCE INTERSECTION IN A SWAMP. PIPE WAS 3.7' ABOVE GRADE, THE TOP 3.5' WAS BENT SOUTH. METAL "T" POST AT 0.1' WEST. WOOD 6" DIA. POST AT 1.0' SOUTH. AREA NOT SUITABLE FOR GPS.

- 1823 Corner first set by Joseph Wampler, U.S. Deputy Surveyor. (P.7)
- 1869 Fairchild, County Surveyor, measures 5244.36' from the east (P.8).
- 1975 Atwell-Hicks, Howard Taft, sets 3/4" X 6' long iron on fenceline. One common witness to the current pipe (P.11).
- 1979 Garlock uses fence corner post for corner, no witnesses (P.12,13).
- 1985 Robert Macomber #27453 (Atwell-Hicks) found 3/4" iron pipe on fenceline intersection, one matching witness to the current pipe (P.14).
- 1992 Desine finds "line rod" at fence intersection, witnesses correspond to the now found pipe (P.15).