

SURVEY & REMONUMENTATION

FEB 25 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

FILED

For corners in

| | | |
|------------------------------------|---|---------------|
| <u>LIVINGSTON</u> (County) | Located in: | Corner Code # |
| 1. Public Land Survey | T1N R4E T4N R5E | <u>H-07</u> |
| 2. Property Controlling in Section | § <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | § <u> </u> T <u> </u> R <u> </u> | <u> </u> |

1998 OCT 14 P 2:10

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

9-
LSC 903M

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JACK K. SMITH, in a field survey on SEPTEMBER 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 16 | | 17 | | 18 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | ● | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1815 WAMPLER SET POST
BLACK OAK 11 N35W 61 (40.3)
WHITE OAK 40 S17E 152 (100.3)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" REROD NORTHEASTERLY OF AN OLD FENCE INTERSECTION. THIS CORNER POSITION AGREES WELL WITH WITNESSES OF RECORD SINCE 1972.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-07 SOUTH 1/4 CORNER SECTION 15 / NORTH 1/4 CORNER SECTION 22, T1N, R4E, PUTNAM TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:
RESET FOUND 1/2" REROD WITH 1 1/4" X 36" STEEL PIPE WITH LIVINGSTON COUNTY REMONUMENTATION BRASS CAP WITH SURVEYOR #35999 @ 1/2 FOOT ABOVE THE SURFACE OF SURROUNDING GROUND.

- S70°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN SOUTH SIDE 24" OAK 16.55'
- S50°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN SE SIDE 30" OAK 7.20'
- WEST NAIL WITH LIVINGSTON COUNTY REMON TAG IN NORTH SIDE 26" OAK 24.98'
- N30°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN SE SIDE TRIPLE 26" OAK 13.35'

Signed by [Signature] Date 9-25-1998

Surveyor's Michigan License No. 35999



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, J.
REVISED MAY 14, 1975 REVISED JAN., 1983
REVISED OCT., 1995

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
DEED GROUP ON 9/16/98 CO. REP JED