

**SURVEY &
REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE

APR 28 1995 Filing Requirement of Act 74, Mich. P.A. 1970

FILED

Nov 16 2 01 PM '94

For corners in

| | | |
|---------------------------------------|---------------------------|-------------------------|
| <u>LIVINGSTON</u> (County) | COMMISSION | Corner Code <u>H-13</u> |
| 1. Public Land Survey | T <u>T1N</u> R <u>R4E</u> | <u>H-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

L.S.C.#353m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DARRELL HUGHES, in a field survey on NOVEMBER 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

PUTNAM TWP.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1823 Joseph Wampler, Deputy Surveyor
White Oak 12" North 75 degrees East 31 links
White Oak 15" North 33 degrees West 18 links

*Additional historical information on back of sheet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner not found. Re-established by extending South line of Section 34 from West 1/8 line 1322.80 ft. East as identified in Atwell-Hicks survey No.561-34, Book 854, Page 2, dated May 10,1985. West 1/8 line corner at South line Section 34 to G-13 = 1322.80 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13, T1N, R4E, PUTNAM, established existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.
090 DEG. 9.74' SET NAIL/TAG S/S 7" MAPLE.
360 DEG. 50.45' SET NAIL/TAG E/S 12" OAK.
282 DEG. 32.80' SET NAIL/TAG N/S 14" OAK.
204 DEG. 52.34' SET NAIL/TAG W/S 22" OAK.

Signed by Darrell Hughes Date 11-8-94

Surveyor's Michigan License No. 19834

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PZER GROUP ON 19 Oct 94



PUTNAM TOWNSHIP, T1N, R4E

H-13, SOUTH 1/4 CORNER SECTION 34, ON BASE LINE.

CORNER NOT FOUND, I propose to establish corner in conformity with previous surveys showing East/West distances between Section corners.

1823 Joseph Wampler, U.S. Deputy Surveyor sets corner, 40 chains from East. P.7.

1973 Atwell-Hicks files Act 74 for G-1 and H-1, Dexter Twp. P.11

1985 Atwell-Hicks survey shows G-1 and H-1 Dexter Twp. P.12