

FILED

Oct 16 11 44 AM '95

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI  
48843

Four corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
Public Land Survey	T <u>1N</u> R <u>4E</u>	<u>I-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

L.S.C. # 499m

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

PUTNAM TWP.

DARRELL HUGHES in a field survey on Oct. 4 ~~JANUARY 23~~, 19 95.  
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therof as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

GLO: 1823, Joseph Wampler, Deputy Surveyor  
White Oak 15" South 46-1/2 degrees West 29 links  
White Oak 12" North 32 degrees East 127 links

SURVEY &  
REMONUMENTATION

NOV 27 1995


Description of corner evidence found and/or method applied in restoring or reestablishing corner  
Found 3/4" iron pipe

COMMISSION

\*Additional descriptions and historical information on back of this sheet.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9, T1N, R4E, PUTNAM, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, all within a road box, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.  
079 DEG. 38.43' SET NAIL/TAG S/S UTILITY POLE.  
158 DEG. 73.14' SET NAIL/TAG SW/S 38" OAK.  
256 DEG. 86.70' SET NAIL/TAG N/S 20" CEDAR.  
293 DEG. 86.03' SET NAIL/TAG SW/S UTILITY POLE.  
325 DEG. 58.71' SET NAIL/TAG NE/S UTILITY POLE.



Signed by Darrell Hughes Date October 5, 1995

Surveyor's Michigan License No. 19834

9-6-95

PUTNAM TOWNSHIP, T1N, R4E

I-9, CORNER COMMON TO SECTIONS 22, 23, 26 AND 27

FIELD: FEBRUARY 1995

FOUND 3/4" IRON PIPE, ABOVE POINTED STONE, 4' EAST OF CENTERLINE SOUTH HOWELL ROAD (PATTERSON LAKE ROAD) AND 5' SOUTH OF CENTERLINE MOWER ROAD. FOUND PK NAIL 9.45' WEST OF IRON PIPE IN ASPHALT PVMT. DISTANCES FROM WITNESS' VARY, HOWEVER EVERYONE IS USING THE PIPE. SEE PAGES 27-29. RAILROAD SPIKE REPLACED WITH PIPE BETWEEN 1965 AND 1971. DISTANCES TO H-9, I-10 AND J-9 AGREE WITH THOMPSON, ROSS AND BOSS. GOOD FOR GPS.

1823 Corner first set by Joseph Wampler, U.S. Deputy Surveyor....."North between 26 and 27...80.00 chains set post common to 22,23,26 and 27" P.7

1838 John Farnsworth survey P.9

1870 Miles Bullock survey P.8

1950 Clay Gordon plats "Read's Acres". P.11A

1956-65 Lyle Munsell uses corner in survey. P.12-12B

1970 Atwel-Hicks plats "Don-Carol Knolls". P.13A

1971 Charles Wilson files Act 74. P.14

1972 Charles Wilson files Act 74. P.16

1972 Robert Jagow files Act 74. P.17

1972 Garlock witness' P18

1976-1979 Francis Papke plats "Portage Dells NO.1&2" P.17A

1979-1987 Boss surveys P.19-22

1990 Brad Thompson surveys and files Act 74. P23-24

1990 Don Ross survey. P.25-25B

1994 Boss survey. P. 26-26A

1995 Corner witness comparisons P.27-29