

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston  
(County)

Located In:

Corner Code #

- |                                    |                           |             |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey              | T <u>1</u> N R <u>4</u> E | <u>I-12</u> |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |

DEC 22 10 13 AM '93  
 NANCY HAVILAND  
 REGISTER OF DEEDS  
 LIVINGSTON COUNTY, MI  
 48843

FILED

L.S.C.# 86m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Darrell D. Hughes, in a field survey on December 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 GLO: 1823  
 Pin Oak 7" S89.5E 2 lks.  
 Pin Oak 15" S74W 25 lks.

\* Additional historical information on back of sheet:

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Fd. 1" iron pipe, 6" below grade of gravel road (Toma Rd.) near its centerline.

SURVEY &  
 MONUMENTATION  
 1993  
 COMMISSION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 I-12, T1N, R4E, PUTNAM, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.  
 145 DEG. 42.04' SET NAIL/TAG SW/S 18" BOX ELDER  
 097 DEG. 59.90' SET NAIL/TAG N/S UTILITY POLE  
 060 DEG. 35.21' SET NAIL/TAG SE/S 30" STUMP  
 276 DEG. 36.48' FD. ANGLE IRON FENCE POST (MEA. TO BASE)  
 097 DEG. 33.05' FD. 3/4" IRON PIPE

Signed by Darrell Hughes Approved by Liv. Co. Peer Group: Nov. 03, 1993  
 Date 12-21-93  
 Surveyor's Michigan License No. 19834

PUTNAM TOWNSHIP, T1N, R4E

I-12, WEST 1/4 CORNER SECTION 35

FIELD 10-21-93

Found 1" iron pipe, 6" below grade of gravel road (Toma Rd.) near its centerline. Found 5 remaining witness marks and calls from previous surveyors. These all checked within reason.

Joseph Wampler first set corner in 1823, Fairchilds, Co. Surveyor used corner in 1852, no witness'.

1955, Lyle Munsell, using witness' by Grant Dunning, fd. corner. 1/2" X 16" rod in cl highway.

1965, Garlock, fd. 3/4" iron pipe, set new witness'

1983, Garlock, fd. 3/4" iron pipe, wit. check.

1983 to present, many surveyors have used corner. There are 4 Act 74 filed: Fahrner, Boss, Stonerock and Garlock. Some copied witness' by others.

Corner is open to sky, occupation to west and east.