

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Livingston</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>1N</u> R <u>4E</u>	<u>J-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**FILED**  
 DEC 27 12 22 PM '93  
 HANCY HAVILAND  
 REGISTER OF DEEDS  
 LIVINGSTON COUNTY, MI  
 48843  
 L.S.C. #114m  
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Darrell D. Hughes a field surveyor on December 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 GLO: 1823  
 Black Oak 12" W47E 33 lks.  
 Black Oak 15" N48.5W 50 lks.

\* Additional historical information on back of sheet:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Fd. 3/8" iron rod in centerline asphalt pavement.

SURVEYOR  
 REMON L. WATSON  
 1993  
 COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 J-11, T1N, R4E, PUTNAM, replaced existing iron rod with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, set cast iron road box over point and is accepted as a careful and faithful reestablishment of the position of the original corner.  
 208 DEG. 91.45' SET NAIL/TAG E/S MBT POLE.  
 310 DEG. 47.22' SET NAIL/TAG NE/S MBT POLE.  
 022 DEG. 84.03' SET NAIL/TAG NW/S UTILITY POLE.  
 080 DEG. 115.93' SET NAIL/TAG S/S UTILITY POLE.

Signed by *Darrell D. Hughes* Approved by Liv. Co. Peer Group: NOV 05 1993  
 Date December 27, 1993  
 Surveyor's Michigan License No. 19834

STATE OF MICHIGAN  
 DARRELL D. HUGHES  
 SURVEYOR  
 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 199 REVISED MAY 14, 1975  
 REVISED JAN., 1983

PUTNAM TOWNSHIP, T1N, R4E

J-11, NORTH 1/4 CORNER SEC. 35

FIELD 10-26-93

Found 3/8" iron rod in centerline asphalt pavement at grade. Dexter-Pinckney Road and Darwin Road. Witness' from former surveyors agree.

Corner first set by Joseph Wampler, 1823

1972, Oscar Boss filed Act 74

1978 and 1985, Garlock used same corner

1981, Pat Benton, use older wit. and sets new (fd. 1/4" iron)

1985, Boss shows same wit. for corner.

Corner open to sky, however fast traffic north and south.