

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 1 N R 4 E</u>	<u>K-04</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

1999 JUN -4 P 12: 56

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #1028m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JACK K SMITH, in a field survey on MARCH 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1825 SIBLEY SET POST
W. OAK 30 N 45 1/2 W 150 (99)
B. OAK 20 N 09 E 191 (126.1)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" REROD 1 FOOT SOUTH OF THE CENTER LINE OF SWARTHOUT ROAD. THIS POSITION AGREES WELL WITH WITNESSES DATING BACK TO 1959 MUNSELL NOTES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-04 EAST 1/4 CORNER SECTION 11, WEST 1/4 CORNER SECTION 12, T1N, R4E, PUTNAM TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:
RESET FOUND 1/2" IRON WITH 1 1/4" X 36" STEEL PIPE WITH BREAKOFF SECTION WITH LIVINGSTON COUNTY REMONUMENTATION BRASS CAP WITH SURVEYOR #35999 @ 1/2 FOOT BELOW THE SURFACE OF BITUMINOUS ROAD IN ROAD BOX 1 FOOT SOUTH OF THE CENTER LINE OF SWARTHOUT ROAD.

N45°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN WEST SIDE 36" OAK
S54°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN NORTH SIDE UTIL. POLE
S05°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN WEST SIDE 30" OAK
S68°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN EAST SIDE 20" OAK
N33°W SOUTHWEST CORNER OF HOUSE AT FOUNDATION

Signed by [Signature]

Date 3-26-1999

Surveyor's Michigan License No. 35999

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 3-3-1999, CO. REP JED

