

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T1N R4E</u>	<u>K-06</u>
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

1999 JUN -4 P 12: 56

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #1030m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JACK K SMITH, in a field survey on MARCH 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1825 SIBLEY SET POST
W. OAK 11 S 52 W 58 (38.3')
B. OAK 13 N 5 1/2 E 116 (76.6')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 3/4" PIPE WITH BENTON CAP IN NORTH-SOUTH FENCE LINE. THIS POSITION AGREES WELL WITH WITNESSES DATING BACK TO 1959 NOTES OF LYLE MUNSELL.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-06 WEST 1/4 CORNER SECTION 13, EAST 1/4 CORNER SECTION 14, T1N, R4E, PUTNAM TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:
RESET FOUND 3/4" PIPE WITH 1 1/4" X 36" STEEL PIPE WITH LIVINGSTON COUNTY REMONUMENTATION BRASS CAP WITH SURVEYOR #35999 @ 1/2 FOOT ABOVE THE SURFACE OF SURROUNDING GROUND 116 FEET NORTHERLY OF THE CENTER LINE OF RUSH LAKE ROAD (GRAVEL) AND 35 FEET EAST OF A PRIVATE DRIVEWAY (GRAVEL).

S22°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN EAST SIDE 26" OAK	18.90'
S35°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN WEST SIDE 10" OAK	31.94'
N35°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN EAST SIDE 24" OAK	5.90'
N12°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN EAST SIDE 36" DBL. OAK	53.10'

Signed by [Signature] Date 3-26-1999

Surveyor's Michigan License No. 35999

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 3-3-1999 CO. REP VED

