

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED 9-

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

1996 NOV 14 P 1:22

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

- | | | | | | |
|------------------------------------|---|-----------|---|-----------|------------|
| 1. Public Land Survey | T | <u>1N</u> | R | <u>4E</u> | <u>K-7</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | |
| | S | | T | | |
| 3. Miscellaneous Property in Sec. | S | | T | | |
| | S | | T | | |

L.S.C.#596m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DARRELL HUGHES, in a field survey on 11-11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

PUTNAM

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1823
Tamarack 5", North 40 degrees East, 910 links
Tamarack 3", North 15 degrees West, 122 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod/cap #6998

*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7, T1N, R4E, PUTNAM, replaced existing corner with 1-1/4" X 36" iron pipe, 10' long, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful perpetuation of the position of the original corner. From date of recon. to setting this corner, the drainage ditches were widened in all directions. This corner is set in water in the drainage ditch, one foot above water surface.

- 273 DEG. 65.31' SET NAIL N/S TWIN 8" CHERRY.
- 070 DEG. 45.65' SET NAIL N/S 10" CHERRY.
- 105 DEG. 47.13' SET NAIL SW/S 12" CHERRY.
- 040 DEG. 48.85' SET NAIL E/S 4" CHERRY.

Signed by Darrell Hughes
Surveyor's Michigan License No. 19834

Date November 11, 1996

PUTNAM TOWNSHIP, T1N, R4E

K-7, CORNER COMMON TO SECTIONS 13, 14, 23 AND 24

FOUND 1/2" IRON ROD WITH CAP #6998, ROBERT JAGOW, ATWELL-HICKS AT SOUTHWEST CORNER OF N-S-E-W DITCH IN MUCK AT SOD FARM. BOSS SET IRON BY OCCUPATION IN 1972, ATWELL-HICKS APPARENTLY RESET IT IN 1973. NO OCCUPATION IN ANY DIRECTION. IRON LEANS TO NORTH. ONE WITNESS AGREES WITH BOSS 1972 ACT 74. OK FOR GPS. I RECOMMEND TO THE PEER GROUP TO ADJUST THE POSITION OF THIS IRON TO MATCH THE BOSS 1972 ACT 74 WITNESS'. IRON WILL MOVE SOUTH 0.5'+\-. MEASURES AGREE SOUTH TO K-8 AND EAST TO L-7.

1823 Corner first set by Joseph Wampler, U.S. Deputy Surveyor.....North between 23 and 24, 80 chains set post (in tamarack swamp).

1972 Oscar Boss sets corner at occupation and files Act 74. P.8

1973 Atwell-Hicks finds and uses corner in survey. P.9

1979 Boss survey copies 1972 witness'. P.10

1982 Boss survey. P. 11

1984 Boss survey. P. 12

1985 Boss survey copies 1972 witness'. P.13

1988 Benton survey, no witness' P.14

1988 Boss survey copies 1972 witness' P.15

1988 Boss survey copies 1972 witness' P.16

1988 Boss survey copies 1972 witness' P.17

1996 Hughes remon. witness' P.18