

FILED

9

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Oct 16 11 43 AM '95

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

or corners in

LIVINGSTON
(County)

Located In:

Corner Code #

Public Land Survey

T 1N R 4E

K-10

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

Property Controlling
In Section

S _____ T _____ R _____

S _____ T _____ R _____

Miscellaneous

S _____ T _____ R _____

Property in Sec.

S _____ T _____ R _____

L.S.C.# 494m

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____

Private Claims _____

DARRELL HUGHES, in a field survey on Oct. 4
JANUARY 24, 19 95

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1, and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

PUTNAM TWP.

SURVEY &
REMONUMENTATION

NOV 27 1995

COMMISSIONER

Description of original monument and accessories and/or subsequent restoration:

GLO: 1823, Joseph Wampler, Deputy Surveyor
White Oak 18", North 64 degrees West, 21 links
Aspen 14", North 72 degrees East, 19 links


Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set corner at East face of fence post

*Additional descriptions and historical information on back of this sheet.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10, T1N, R4E, PUTNAM, established corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.
324 DEG. 9.21' SET NAIL NE/S 14" HICKORY.
010 DEG. 15.44' SET NAIL W/S 12" BASSWOOD.
067 DEG. 22.47' SET NAIL S/S 4" HICKORY.
154 DEG. 20.72' SET NAIL W/S 6" MAPLE.



Signed by Darrell Hughes Date October 5, 1995

Surveyor's Michigan License No. 19834

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

PL 345 1990, APPROVED BY LIVINGSTON COUNTY
X-16-95

PUTNAM TOWNSHIP, T1N, R4E 1/4 21E 1860' VILLAGED BA FANGSUCH CONNIA

K-10, EAST 1/4 COR. SEC. 26, WEST 1/4 COR. SEC. 25

FIELD: FEBRUARY 1995

FOUND CORNER FENCE POST WITH WIRE N, S, E AND WEST. ALSO FOUND 1/2" IRON ROD WITH CAP #13574 (SET BY BOSS IN 1974, P.13) 2.5' EAST OF ABOVE FENCE POST. P.20 GARLOCK USES FENCE POST 1969 P.11. BOSS SETS IRON "AT FENCE INTERSECTION OCCUPATION" IN 1974, FILES ACT 74 FOR SAME IN 1976. GARLOCK IN 1985 FINDS FENCE POST AGAIN BUT NOW WITH BOSS IRON 2.2' EAST OF POST. THE SURVEY STATES THE EAST 1/4 CORNER IS "CORNER POST SET IN STONE". P.17 GARLOCK IN 1994 SHOWS 1/2" IRON TO BE CORNER...SHOWS BOSS WITNESS'. POOR FOR GPS. I WILL SET CORNER AT EAST FACE OF FENCE POST, 2.2' WEST OF BOSS IRON.

1823 Corner first set by Joseph Wampler, U.S. Deputy Surveyor....."North between 25 and 26, 40 chains, set 1/4 post" P.7

1871 Miles Bullock surveys Section 26. P.8

1874 Miles Bullock surveys Section 25. P.9

1974 Oscar Boss sets "1/2" iron". P.13

1976 Oscar Boss files Act 74 for above. P.15

1985 Charles Garlock shows "East 1/4 corner Section 26 is corner post set in stone."

1994 Garlock shows 1/2" iron rod 2.2' East of post to be corner. P. 19

1995 Hughes field witness' and comparison. P.20