

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>1N</u> R <u>4E</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property In Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

DEC 27 12 22 PM '93
 NANCY HAVILLAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48643

FILED

L.S.C. #113
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Darrell D. Hughes, in a field survey on December 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO: 1823
- Black Oak 10" N9W 4 lks.
- Black Oak 13" N73E 18 lks.

*Additional historical information on back of sheet:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1/2" iron rod with cap: No. 13574.

SURVEY
 REMONUMENTED
 1993
 COMMISSION

-C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11, T1N, R4E, PUTNAM, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.
 050 DEG. 1.10' SET NAIL/TAG W/S 6" TWIN CHERRY.
 180 DEG. 36.25' SET NAIL/TAG W/S 6" ELM.
 265 DEG. 62.25' SET NAIL/TAG S/S 18" MULTI-TRUNK TREE.
 280 DEG. 90.70' SET NAIL/TAG N/S 30" TREE.
 180 DEG. 38' +/- NORTH EDGE POND

Signed by Darrell D. Hughes Approved by Liv. Co. Peer Group NOV 10 1993
 Date December 27, 1993
 Surveyor's Michigan License No. 19834

STATE OF MICHIGAN
 REGISTERED LAND SURVEYOR
 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 23, 1971
 (REVISED MAY 74, 1975)
 (REVISED JAN, 1983)

PUTNAM TOWNSHIP, T1N, R4E

K-11, NE COR. SEC. 35

FIELD 10-26-93

Found 1/2" iron rod with cap no. 13574, Oscar Boss. Corner at Darwin Road PI. In side lawn, sw of house and north of pond. Witness' check with Act 74, no.940, 1976. and Garlock witness' in 1978.

Joseph Wampler first set corner in 1823

1871, Miles Bullock used corner to measure S. line Sec. 26 (78.70 chains)

1969, Munsell & Garlock show corner on survey.

1970, Boss shows corner on survey.

1972, Garlock

1976, Boss files Act 74

1980, Benton used corner, distance or wit. not shown.

1985, Garlock shows witness' of Boss and adds to.

corner is next to cherry tree. sky blocked for GPS. No occupied lines in any direction, has always been same ownership on all sides.

111