

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

FILED  
 DEC 22 10 13 AM '93  
 HANCOCK HAVILLAR  
 REGISTER OF DEEDS  
 LIVINGSTON COUNTY, MI  
 48843

For corners in

|                                       |                         |                |
|---------------------------------------|-------------------------|----------------|
| <u>Livingston</u><br>(County)         | Located In:             | Corner Code #/ |
| 1. Public Land Survey                 | T <u>1N</u> R <u>4E</u> | <u>K-13</u>    |
|                                       | T _____ R _____         | _____          |
|                                       | T _____ R _____         | _____          |
|                                       | T _____ R _____         | _____          |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____ | _____          |
|                                       | S _____ T _____ R _____ | _____          |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____ | _____          |
|                                       | S _____ T _____ R _____ | _____          |

L.S.C.# 87m  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

I, Darrell D. Hughes, in a field survey on December 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1819  
 White Oak 24" N39W 17 lks.  
 White Oak 6" N78.5E 25 lks.

\* Additional historical information on back of sheet:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1-1/2" pipe monument.

SURVEY &  
 REMONUMENTATION  
 1993  
 COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13, T1N, R4E, PUTNAM, existing physical concrete monument corner remains, set atop with 1-1/4" X 30" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.  
 099 DEG. 76.30' SET NAIL/TAG N/S 36" OAK  
 208 DEG. 53.90' SET NAIL/TAG E/S 24' OAK  
 185 DEG. 24.90' FD. 1/2" IRON ROD/CAP #19005  
 314 DEG. 87.79' SET NAIL/TAG NE/S 16" OAK  
 033 DEG. 89.23' SET NAIL/TAG NW/S 12" OAK

igned by Darrell D. Hughes Approved by Liv. CO. Peer Group: Nov 20, 1993  
 Date 12-21-93  
 Surveyor's Michigan License No. 19834

PUTNAM TOWNSHIP, T1N, R4E

K-13, SOUTHWEST CORNER SEC. 36

FIELD 10-26-93, 11-16-93 D.D.HUGHES AND ASSOCIATES

Found 1-1/2" pipe monument 36" below grade of gravel road (Sarah), 14' East of centerline of Earl St., 377.14' West of found 3/4" iron pipe for K-1, Dexter Twp., Washtenaw Co.. Found two witness trees for LSC #616, (no nails). RLS#6998.

Joseph Wampler first set corner in 1819.

1908, Plat of "Baughn Bluff", Grant Dunning "...set 1/4" X 59" gas pipe on base line 11.78 chains(777.48') East from Southwest corner Sec. 36.

1941, Plat of "Beulah Beach" shows corner as tag line, same as above.

1969, Garlock, fd. 1/2" iron and witnessed.

1973, Jagow files Act 74, fd. 1-1/2" pipe with 1/2" rebar.

1988, Boss survey showing Jagow witness'. Corner is corner for "Portage Bay Highlands No.2" subdivision.

Corner falls in gravel rd. intersection (Earl and Sarah) Tall trees surround intersection. No occupation lines evident. Set 30" standard Livingston County Remonumentation monument above.