

9-

FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

1. Public Land Survey

T 1 N R 4E L-7

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

1996 NOV 14 P 1:22

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #597m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DARRELL HUGHES, in a field survey on 11-8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

PUTNAM

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1823
Black Oak 16", South 81-1/2 degrees East, 465 links
White Oak 15", North 67-1/2 degrees West, 525 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 3" x 5" x 3ft. high concrete post

*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7, T1N, R4E, PUTNAM, drilled hole in top center of existing concrete corner, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful perpetuation of the position of the original corner.
295 DEG. 30.81' SET NAIL/TAG N/S 10" WILLOW.
272 DEG. 29.21' SET NAIL/TAG N/S 10" WILLOW.
105 DEG. 63.97' SET NAIL/TAG N/S TWIN 5" TREE.
047 DEG. 260.60' SET NAIL/TAG W/S 10" OAK.
035 DEG. 173.97' CL CONSUMERS POWER GAS LINE MARKER.

Signed by Darrell Hughes
Surveyor's Michigan License No. 19834

Date November 8, 1996

P.A. 345 1980, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 9-18-96 CO. REP JED

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT 1995

PUTNAM TOWNSHIP, T1N, R4E

L-7, NORTH 1/4 COR. SEC. 24 AND SOUTH 1/4 COR. SEC. 13

FIELD: 9-17-1996

FOUND 3" X 5" CONCRETE UPRIGHT POST, 3' ABOVE GRADE IN LOW SWAMPY AREA. POST HAS NO IRON ROD. MEASURES FROM TOP CENTER OF THIS POST WEST TO K-7 AND SOUTHWEST TO K-8 AGREE WITH ATWELL-HICKS, BENTON AND BOSS SURVEYS. NO OCCUPATION IN ANY DIRECTION. COULD NOT FIND WHO SET THIS POST. I RECOMMEND TO THE PEAR GROUP THE ACCEPTANCE OF THIS POST FOR THE LOCATION OF L-7. I WILL DRILL A 1/2" HOLE AND EPOXY IN A 1/2" IRON ROD AFFIXED WITH A BRASS LIV. CO. REMON. MONUMENT CAP.

1823 Corner first set by Joseph Wampler, U.S. Deputy Surveyor, 39.80 chains East of K-7. P.7

1837-1913 County surveyor witness'. P.8

1840 Amos Adams, county surveyor, surveys in NW1/4. P.9

1880 Miles Bullock, county surveyor, surveys in NE1/4. P.10

1959 Lyle Munsell witness to corner. P.12

1973 Atwell-Hicks finds corner in survey. no witness'. P.11

1979 Boss survey said they did not locate but calculated location from Atwell-Hicks survey. P.13

1988 Patrick Benton uses corner in survey. P. 14 No witness' on survey see field note witness' P.14C

1988 Boss survey. All other 5 corners are witnessed except this one. P.15

1996 Hughes field witness'. find comparison with Benton on page 14C. P.16