

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

9

For corners in

Livingston
(County)

Located In:

Corner Code #/

1. Public Land Survey	T	<u>1N</u>	R	<u>4E</u>	<u>L-11</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

DEC 22 10 13 AM '93
NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

FILED

L.S.C.# 88m

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Darrell D. Hughes a field surveyor on December 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
GLO: 1823
Ash 7" N12E 89 lks.
Elm 3" N77W 15 lks.

*Additional historical information on back of sheet:

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Fd. 1/2" iron rod (no cap) in maple swamp.

SURVEY &
REMONUMENTATION
1993
COMMISSION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-11, T1N, R4E, PUTNAM, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.
010 DEG. 45.25' SET NAIL/TAG W/S 16" MAPLE
215 DEG. 18.70' SET NAIL/TAG W/S TWIN 12" MAPLE
240 DEG. 31.63' SET NAIL/TAG SE/S 18" MAPLE
120 DEG. 16.82' SET NAIL/TAG N/S 20" MAPLE

Signed by Darrell Hughes Approved by Liv. Co. Peer Group, Nov. 03, 1993
Date 12-21-93
Surveyor's Michigan License No. 19834

PUTNAM TOWNSHIP, T1N, R4E

L-11, NORTH 1/4 CORNER SECTION 36

FIELD 10-26-93

Found 1/2" iron rod (no cap) in maple swamp, 0.20' Southeast from 6" diameter (new) treated post 5' tall, with a flat side facing Northwest. Inscribed in flat face 3" tall lettering " S.1/4 SEC.25, T1N,R4E". Boss and Garlock witness' check to fd. iron.

Joseph Wampler set original corner in 1823.

1874, Miles Bullock, subdivided Section 25, to north, (Survey No. 25)

1974, Boss survey, Act 74 recorded in 1976. 1/2" iron fd.

1980, Benton shows corner on survey, no witness'.

1980, Garlock identifies East 1/8 line Section 36, shows new witness' for corner with (older) guard post.

1991, Boss identifies corner in CLS #4663.

Corner is in Maple swamp with overhead tree canopy blocking sky. Ground is spongy with standing water. Access is from West 500' off of N/S private trail. Lone house sets approx. 400' north of E/W section line and 600' West of N/S 1/4 line. House 900' S. of Darwin Rd.