

FEB 24 1998

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1997 NOV 13 P 1:44

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

L.S.C.#791m

Register of Deeds Stamp & File Number

For corners in:

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1</u> N <u>R</u> 4 E	<u>M-2</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

DARRELL D. HUGHES, in a field survey on OCTOBER 27, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

PUTNAM TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor  
White Oak 16" South 77 degrees West 33 links  
White Oak 14" North 8 degrees East 44 links

\* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod at intersection of North, South and West fences and 350± East of centerline of North/South pipeline corridor.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2, T1N, R4E, PUTNAM, replaced existing corner with 1 1/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 203 deg. Set Nail / Tag E/S 8" Cherry 13.79'
- 247 deg. Set Nail / Tag SE/S 24"-14" Dbl. Hickory 20.96'
- 337 deg. Set Nail / Tag E/S 10" Hickory 20.63'
- 040 deg. Set Nail / Tag SE/S 8" Walnut 19.12'

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 10-1-97, CO. REP JED

Signed by Darrell D. Hughes  
Surveyor's Michigan License No. 19834

Date OCTOBER 27, 1997

PUTNAM TOWNSHIP, T1N, R4E

M-2, EAST 1/4 CORNER SECTION 1

FIELD: 9-29-1997 DARRRELL HUGHES AND ASSOCIATES, LAND SURVEYORS

FOUND 1/2" IRON ROD (NO CAP) 0.15' ABOVE GROUND GRADE AT INTERSECTION OF NORTH, SOUTH AND WEST FENCING, 350' EAST OF NORTH-SOUTH PIPE LINE CORRIDOR. TWO FORMER WITNESS' CHECK, MUNSELL, BOSS, DESINE AND HUGHES HAVE USED THIS CORNER IN SURVEYS, LOOKED FOR A-2, HAMBURG AT 145' NORTH OF THIS IRON (P.9A-9B), DID NOT FIND AND THERE IS NO OCCUPTION TO EAST. I RECOMMEND, TO THE PEER GROUP, THE ACCEPTANCE OF THIS POINT AS THE LOCATION OF M-2, POOR FOR GPS.

- 1823 CORNER FIRST SET BY JOSEPH WAMPLER, U.S. DEPUTY SURVEYOR....."NORTH ON THE EAST BOUNDARY OF SECTION 1, 40.00 CHAINS; SET 1/4 SECTION POST", P.7-7B
- 1880 MILES BULLOCK, COUNTY SURVEYOR, SURVEYS IN SECTION 1, PUTNAM AND IN SECTION 6, HAMBURG. SHOWS A-1 TO BE 145.2' NORTH OF M-2. P.8, 9-9B
- 1968 LYLE MUNSELL, SURVEYS E 1/2 OF NE 1/4 SECTION 1, SHOWS CORNER AT NORTH-WEST FENCE INTERSECTION. MEASURES NORTH TO A-1 ARE WITHIN 10 FEET OF BULLOCK'S 1880 SURVEY. P.10
- 1975-1991 BOSS ENGINEERING USES CORNER IN VARIOUS SURVEYS, SAME WITNESS' ON ALL SURVEYS. P.11 THRU P.17A
- 1992 HUGHES USES CORNER IN RETRACEMENT OF PARCEL LINE (NORTH LINE OF PARCEL B, P.11), DOES NOT IDENTIFY CORNER OR SHOW WITNESS'. P.18
- 1993 DESINE USES CORNER IN SURVEY, SHOWS FORMER AND SETS NEW WITNESS'. P.19-19B
- 1997 HUGHES WITNESS COMPARISON LIST. P.20-20A