

SURVEY & REMONUMENTATION

FEB 24 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

1997 NOV 13 P 1:44

NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI.
 48843

L.S.C.#792m

Register of Deeds Stamp & File Number

For corners in **SECTION**

LIVINGSTON
 (County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---------------|-----------------------------|-------------|
| 1. Public Land Survey | | <u>T 1 N R 4 E</u> | <u>M-3</u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

PUTNAM TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
 White Oak 14" South 52 degrees West 3.76 links
 White Oak 12" North 18 degrees West 3.75 links

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner not found. Reconstructed position to fit surrounding surveys.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 T1N, R4E, PUTNAM, set corner with 1 1/2" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 071 deg. Set Nail / Tag N/S 14" Elm E/edge of swamp 93.01'
- 185 deg. Set Nail / Tag W/S 18" Ash S/edge of swamp 163.98'
- 272 deg. Found 1/2" iron rod with cap #17022 289.98'
- 359 deg. Found 1/2" iron rod with cap #17022 234.99'

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 10-10-97 CO. REP JED

Signed by *Darrell D. Hughes*

Date NOVEMBER 3, 1997

Surveyor's Michigan License No. 19834

PUTNAM TOWNSHIP, T1N, R4E

M-3, SOUTHEAST CORNER SECTION 1 AND NORTHEAST CORNER SECTION 12.

FIELD: 9-29-1997 AND 10-6-1997

NO RECORDED WITNESS' EXIST FOR THIS POINT, EXCEPT ORIGINAL GLO. CORNER NOT FOUND, FALLS IN MIDDLE OF A DELIGHTFUL 400' DIAMETER TREELESS, BRUSHLESS AND SOLID BOTTOM SWAMP, WATER 1.5' DEEP. SWEEPED AREA WITH LOCATER. NO EVIDENCE, SUCH AS FENCING, ROCK PILE AND/OR POST, FOUND. DISTANCES SHOWN ON VARIOUS OLDER SURVEYS FROM THIS CORNER TO THE NORTH, SOUTH AND WEST MUST HAVE BEEN CALCULATED, BUT WAS NOT SO STATED. IN 1997, BOSS ENGINEERING, RECONSTRUCTED THIS CORNER FROM THE EAST 1/8 LINE AT FARLEY ROAD AND FROM M-2, TO THE NORTH. WE TRAVERSED A LINE FROM M-2 TO M-4, INCLUDING IN THE TRAVERSE, THE 1997 BOSS REFERENCE TRAVERSE POINTS (PAGE 17) SET ON THE SOUTH LINE OF SECTION 1, 289.98' WEST OF M-3 AND ON THE EAST LINE OF SECTION 1, 234.99' NORTH OF M-3, BOTH POINTS BEING AT THE SWAMP'S EDGE. OUR MEASURES NORTH TO M-2 AND WEST TO THE 1/8 LINE IRON AGREE WITH THE 1997 BOSS SURVEY. OUR MEASURES SOUTH TO M-4 ARE 0.87' SHORT, COMPARED WITH THE 1970 MINSSELL SURVEY. NOTHING FOUND FOR A-3, 145.20' (GLO) NORTH. I RECOMMEND, TO THE PEER GROUP, THE ACCEPTANCE OF THE CALCULATED CORNER LOCATION, AS SHOWN ON THE 1997 BOSS SURVEY. WE WILL SET A MONUMENTATION PIPE AND CAP IN THE SWAMP, USING THE TWO BOSS IRONS ALONG WITH NAILS IN TREES AS WITNESS'.

- 1823 JOSEPH WAMPLER FIRST SETS CORNER...."NORTH ON THE EAST BOUNDARY OF SECTION 12, 80.00 CHAINS SET POST". AND FOR A-3...."WEST BETWEEN SECTIONS 6 AND 7 (HAMBURG) 84.65 CHAINS, INTERSECTED WEST BOUNDARY 2.20 CHAINS (145.20') NORTH OF POST (M-3). P.7-7C
- 1845-1905 COUNTY SURVEYOR'S SECTION MEASURES AND WITNESS'. NOTHING STATED FOR M-3. P.8-8C
- 1945 SKETCH OF SECTION 7, HAMBURG BY CLAY GORDON. P.9
- 1970 SURVEY BY OSCAR BOSS SHOWS TRIANGLE FOR CORNER, NO WITNESS' OR DESCRIPTION. P.10-10A
- 1970 SURVEY BY LYLE MINSSELL SHOWS CORNER, NO WITNESS' OF DESCRIPTION. P.11-11A
- 1977 GARY BOSS SHOWS CORNER IN SURVEY, NO WITNESS', NO DESCRIPTION. P.12-12A
- 1978-1995 BOSS SURVEYS SHOWING CORNER. P.13-16
- 1997 BOSS SURVEY DEFINES CORNER WITH WITNESS'. P17-17A
- 1997 HUGHES M-2, M-3, M-4 TRAVERSE. P.18