

SURVEY & REMONUMENTATION

FEB 24 1998

FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1997 NOV 13 P 1:44

HANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #793m

Register of Deeds Stamp & File Number

For corners in **SECTION**

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1</u> N <u>R</u> 4 E	<u>M-4</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

DARRELL D. HUGHES, in a field survey on OCTOBER 27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				1
3													
4	7		8		9		10		11				12
5													
6	18		17		16		15		14				13
7													
8	19		20		21		22		23				24
9													
10	30		29		28		27		26				25
11													
12	31		32		33		34		35				36
13													

PUTNAM TWP.

Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
White Oak 9" South 53 degrees West 43 links
White Oak 8" North 30 degrees West 18 links

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Square Headed Bolt 722± North of the centerline of Swarthout Road along a North/South Private drive.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4, T1N, R4E, PUTNAM, replaced existing corner with 1 1/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 140 deg. Set Nail / Tag N/S Power pole 4.55'
- 285 deg. Set Nail / Tag S/S 15" Box Elder 10.48'
- 303 deg. Set Nail / Tag NE/S 6" Oak 17.08'
- 330 deg. Set Nail / Tag E/S 12" Oak 15.54'
- 002 deg. Found 1/2" iron rod for A-4 T2N-R5E, Hamburg Twp. 114.90'

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 10-1-97, CO. REP JED

Surveyed by [Signature]
Surveyor's Michigan License No. 19834

Date OCTOBER 27, 1997

PUTNAM TOWNSHIP, TIN, R4E

M-4, EAST 1/4 CORNER SECTION 12

FIELD: 9-29-1997 DARRELL HUGHES AND ASSOCIATES, LAND SURVEYORS

FOUND SQUARE HEADED BOLT, 0.2' ABOVE GROUND GRADE AT CENTERLINE TREE ROW TO NORTH AND AT END OF FENCE TO SOUTH. FORMER CONCRETE FALLEN END POST (FOUND IN 1995) NOW REMOVED. BOLT LEANS 0.5' +/- TO SOUTH. MEASURES NORTH TO FOUND 1/2" IRON ROD FOR A-4 IS 115.17'. GLO DISTANCE IS 118.14'. I MEASURED 114.35' IN 1995, HOWEVER WITNESS' AGREE WITH 1995 POSITION. I RECOMMEND, TO THE PEER GROUP, TO ADJUST THE POSITION OF THIS CORNER BY THE FOLLOWING METHOD: SET CORNER 114.90' SOUTH OF FD. 1/2" IRON ROD AT A-4 ON LINE WITH A-4 AND IRON ROD 125.00' NORTH OF A-4, PER GARLOCK SURVEY (PAGE 24) AND HUGHES SURVEY OF 1995 (PAGE 25). MARGINAL FOR GPS.

- 1823 CORNER FIRST SET BY JOSEPH WAMPLER, U.S. DEPUTY SURVEYOR....."NORTH ON THE EAST BOUNDARY OF SECTION 12, 40.00 CHAINS, SET 1/4 SECTION POST". P.7-7A
- 1853 EZRA FAIRCHILDS SURVEYS IN SECTIONS 6 AND 7 HAMBURG. P.8
- 1889 ISAAC TELLER SHOWS FALLING TO BE 114.84'. P.9
- 1945 CLAY GORDON SKETCHES WEST 1/2 OF SECTION 7, HAMBURG. P.10
- 1966 LYLE MUNSELL SURVEYS E 1/2 OF SE 1/4 SECTION 12. P.11
- 1967 LYLE MUNSELL SHOWS FALLING BETWEEN M-4 AND A-4. P.12
- 1970 CONSUMERS POWER SURVEYORS FIND CORNER. P.13-13B
- 1970 LYLE MUNSELL FINDS CORNER. P.14
- 1971 CHARLES GARLOCK SHOWS CORNER IN SURVEY. P.15-51A
- 1972 OSCAR BOSS SHOWS FALLING IN SURVEY. P.16
- 1972 CHARLES GARLOCK SHOWS FALLING IN SURVEY. P.17-17B
- 1973 PAT BENTON DESCRIBES CORNER AS BOLT AND SHOWS WITNESS'. P.18
- 1974 OSCAR BOSS WITNESS' A-4. P.19-19A
- 1974-1977 OSCAR BOSS SHOWS FALLING AND WITNESS' M-4 AND A-4. P. 20-20B
- 1977 PAT BENTON DESCRIBES A-4. P. 21
- 1978 CHARLES GARLOCK SHOWS FALLING, P. 22
- 1991 GARY BOSS SHOWS CORNER IN SURVEY. P.23
- 1994 GARLOCK SHOWS A-4 IN SURVEY AND HINTS AT M-4 AS ANGLE POINT IN BOUNDARY. P.24
- 1995 HUGHES RETRACES GARLOCK SURVEY AND SHOWS FALLING. NO WITNESS, EXCEPT IN FIELD NOTES. P. 25
- 1996 BOSS RECONSTRUCTS LINE BETWEEN M-4 AND A-5. SHOWS FALLING BETWEEN M-4 AND A-4. P.26
- 1997 HUGHES WITNESS COMPARISON LIST. P. 27-27C