

SURVEY & REMONUMENTATION

FEB 24 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

1997 NOV 13 P 1:44

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C.#794m

Register of Deeds Stamp & File Number

For corners in SECTION

<u>LIVINGSTON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>1</u> N <u>R</u> 4 E	M-5
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DARRELL D. HUGHES, in a field survey on OCTOBER 27, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

PUTNAM TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
Black Oak 5" South 85 degrees West 17 links
White Oak 20" North 80 degrees West 27 links

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" iron rod at North, East (downed) and West (downed) fence intersection.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5, T1N, R4E, PUTNAM, replaced existing corner with 1 1/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 017 deg. Found iron rod (painted yellow) at North, South and West fence intersection 326.45'
- 110 deg. Set Nail / Tag S/S 12" Hickory 22.04'
- 157 deg. Set Nail / Tag W/S Dead tree 31.37'
- 275 deg. Set Nail / Tag N/S 10" Hickory 17.21'
- 284 deg. Set Nail / Tag N/S 30" Hickory 37.34'
- 310 deg. Set Nail / Tag S/S 14" Birch 22.26'
- 010 deg. Found iron rod with cap #13574 for A-5 T1N,R5E Hamburg Twp. 85.15'

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 10-10-97, CO. REP JED

Surveyed by Darrell Hughes
Surveyor's Michigan License No. 19834

Date OCTOBER 27, 1997

PUTNAM TOWNSHIP, T1N, R4E

M-5, SOUTHEAST CORNER SECTION 12 AND NORTHEAST CORNER SECTION 13.

FIELD: 9-29-1997 D. D. HUGHES AND ASSOCIATES, LAND SURVEYORS

FOUND 5/8" IRON ROD, 0.4' ABOVE GROUND GRADE AT WEST, NORTH, EAST FENCE INTERSECTION, IN MICK. 326.45' TAPED (327.45' RECORD [MINSSELL] P.10A) SOUTH OF FOUND 1/2" IRON ROD (TOP PAINTED YELLOW) AT NORTH AND WEST FENCE INTERSECTION (SEE 1997 FIELD SKETCH P.23C). FOUND FOUR EXISTING WITNESS NAILS IN TREES, ONLY ONE AGREES WITH BOSS WITNESS. FOUND 1/2" IRON ROD WITH OSCAR BOSS CAP, 85.15' NORTH (91.08' GLO) FOR A-5, WITNESS' SHOWN ARE FOR M-5, PUTNAM, NOT A-5, HAMBURG. POOR FOR GPS. I RECOMMEND, TO THE PEER GROUP, THE ACCEPTANCE OF THIS 5/8" IRON ROD FOR THE LOCATION OF M-5, BASED ON THE FOLLOWING:

- 1823 CORNER FIRST SET BY JOSEPH WAMPLER, U.S. DEPUTY SURVEYOR.... "NORTH ON THE EAST BOUNDARY OF SECTION 13, 80.00 CHAINS, SET POST". AND "WEST BETWEEN SECTIONS 7 AND 18, (HAMBURG) 84.55 CHAINS, INTERSECTED WEST BOUNDARY 1.38 CHAINS (91.08') NORTH OF POST". P.7-7C
- 1837-1910 COUNTY SURVEYOR'S SECTION WITNESS'. P.8-8C
- 1945 CLAY GORDON SKETCH OF SECTION 7, HAMBURG. P.9
- 1966 LYLE MINSSELL SURVEY OF E 1/2 OF SE 1/4 SEC. 12. NO WITNESS'. P.10-10A
- 1970 CONSUMERS POWER SHOWS CORNER, NO WITNESS'. P.11-11B
- 1971 GARLOCK SHOWS CORNER, NO WITNESS'. P.12
- 1973 JOHN SNYDER FILES ACT 74 FOR CORNER. WITNESS SHOW ARE NOT FOR THIS CORNER. P.13
- 1973 PAT BENTON SHOWS CORNER IS SURVEY WITH WITNESS'. DOES NOT SHOW FALLING. P.14
- 1974 OSCAR BOSS SHOWS A-5 IN SURVEYS AND FILES ACT 74. DOES NOT SHOW FALLING. P.15-17
- 1975 PAT BENTON USES CORNER AGAIN IN SURVEY, NO WITNESS'. P.18-18B
- 1989 DAVID FINNEY SHOWS CORNER IN MORTGAGE REPORT. P.19
- 1990 GARY BOSS SHOWS A-5 IN SURVEY WITH WITNESS'. P.20-20A
- 1991 GARY BOSS SHOWS M-5 IN SURVEY, NO WITNESS'. P.21-21A
- 1995 GARY BOSS SHOW A-5 IN SURVEY. P.22-22A
- 1997 HUGHES WITNESS COMPARISON LIST. P.23-23C