

9-
FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1N R 4E M-7
 T ___ R ___ _____
 T ___ R ___ _____
 T ___ R ___ _____
- 2. Property Controlling S ___ T ___ R ___ _____
 in Section S ___ T ___ R ___ _____
- 3. Miscellaneous S ___ T ___ R ___ _____
 Property in Sec. S ___ T ___ R ___ _____

1996 NOV 14 P 1:20

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C.#573m

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, DARRELL HUGHES, in a field survey on 11-8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

PUTNAM

- A. Description of original monument and accessories and/or subsequent restoration:
 GLO: 1823
 White Oak 15", South 48 degrees West, 124 links
 White Oak 20", North 56 degrees West, 161 links

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found axle shaft

*Additional descriptions and historical information on back of this sheet.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-7, T1N, R4E, PUTNAM, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful perpetuation of the position of the original corner.
 187 DEG. 22.98' SET NAIL/TAG W/S 8" CHERRY.
 276 DEG. 3.97' SET NAIL/TAG S/S 24" CHERRY.
 145 DEG. 101.99' SET NAIL/TAG W/S 60" OAK.
 072 DEG. 61.15' SET NAIL/TAG NW/S 8" POPLAR.

Signed by *Darrell Hughes*
 Surveyor's Michigan License No. 19834

Date November 8, 1996

PUTNAM TOWNSHIP, T1N, R4E

M-7, NORTHEAST CORNER SECTION 24 AND SOUTHEAST CORNER SECTION 13.

FIELD: JUNE 1996

FOUND AUTO AXLE SHAFT 20' WEST OF THE WEST EDGE N/S GRAVEL ROAD (KINGSTON DRIVE) ON TREE LINE TO WEST. FOUND MONUMENT FOR SE COR. "KINGSTON ESTATES" SUBDIVISION. 141.47' M., 141.51' R. OLDER WITNESS' AGREE. MEASURES WEST TO L-7 ARE 50' SHORT FROM BOSS SURVEY P.14, MEASURES SOUTH TO A-8 AGREE. P.17. I RECOMMEND THE LOCATION OF THIS AXLE SHAFT FOR THE PERPETUATION OF M-7.

1823 CORNER FIRST SET BY JOSEPH WAMPLER, U.S. DEPUTY SURVEYOR. P.7-7C.

1837-1910. COUNTY SURVEYOR CORNER WITNESS'. P.8-8A.

1880 MILES BULLOCK, COUNTY SURVEYOR, SURVEYS NE1/4 SEC. 24. P.9-9A.

1938 CLAY GORDON SETS AXLE SHAFT. P.10

1965 LYLE MINSSELL USES CORNER IN SURVEY. P.11

1974 GARY BOSS PLATS PARCELS 7 & 8 OF MINSSELL SURVEY. "KINGSTON ESTATES". USES AXLE SHAFT. P.12

1974 OSCAR BOSS MISTAKES AXLE SHAFT FOR A-7 HAMBURG AND SETS IRON 88.44' SOUTH OF SHAFT FOR M-7. FILES ACT 74 P.13

1988 BOSS SURVEY USES IRON ROD SET BY OSCAR ABOVE. P.14-14B

1988 BOSS SURVEY USES AXLE FOR CORNER. P.15-15A

1989 BOSS SURVEY USES AXLE FOR CORNER. P.16-16B

1990 BOSS SURVEY USES AXLE AND SHOWS DISTANCE TO A-8, HAMBURG TWP. P.17-17A