

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

9-

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

1996 NOV 14 P 1:20

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C.#574m

Register of Deeds Stamp & File Number

1. Public Land Survey

T 1N R 4E M-8

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, DARRELL HUGHES, in a field survey on 11-8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

PUTNAM

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1823
Red Oak 20", South 63-3/4 degrees ---, 306 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" diameter steel pipe 5 ft. above water

*Additional descriptions and historical information on back of this sheet.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8, T1N, R4E, PUTNAM, left 2" diameter steel pipe in place. Set two, one inch diameter witness pipes, with 2" dia. brass caps stamped "Livingston Co. Monumentation Witness" P.S. 19834, one witness pipe being 40' North of M-8 on the M-8 / M-7 line and the second witness pipe being 120' West of M-8 on the M-8 / K-8 line and is accepted as a careful and faithful perpetuation of the position of the original corner.

SEE REVERSE FOR WITNESS INFORMATION AND SKETCH.

Signed by Darrell Hughes
Surveyor's Michigan License No. 19834

Date November 8, 1996



PUTNAM TOWNSHIP, T1N, R4E

M-8, EAST 1/4 CORNER SECTION 24 ON TOWNSHIP LINE

FIELD: 6-28-1996

FOUND 2" DIAMETER STEEL PIPE IN STANDING WATER IN SWAMP. WATER 2-3' FEET DEEP, PIPE STANDING 5 FEET ABOVE WATER. PROBED AROUND BASE OF PIPE AND FOUND NO OTHER OBJECT. NO WITNESS' FOUND. MEASUREMENT NORTH FROM TOP CENTER TO A-8 (2" PIPE) HAMBURG IS 120.96' (COMPUTED GLO 121.11'), MEASURES WEST TO MONUMENT IN "PINCKNEY SCHOOL ACRES" SUB. AT SCHOLAR DRIVE CHECKS. MEASURES SOUTH TO THE SOUTHEAST CORNER OF SUB IS 1' LONG. I RECOMMEND, TO THE PEER GROUP, THE ACCEPTANCE OF THE 2" PIPE FOR THE LOCATION OF M-8, AND, AS THIS LOCATION IS ALWAYS UNDER WATER, I RECOMMEND SETTING REFERENCE POINTS 40' NORTH ON THE M-7 \ M-8 LINE AND 120' WEST ON THE M-8 \ K-8 LINE.

- 1823 Corner first set by Joseph Wampler, U.S. Deputy Surveyor....North on East boundary of Sec. 24, 40 chains, set post. P.7
- 1837 Amos Adams survey. P.8
- 1880 Miles Bullock survey. P.9
- 1973 Boss survey, no witness', "point in marsh" P.10
- 1988 Boss survey, no witness', "in swamp, inaccessible". P.11
- 1990 & 1993 Boss survey ties A-8 Hamburg into cl M-36. P.12-13
- 1981 "Pinckney School Acres" sub. ties in to M-8. P.14
- 1928 MDOT ROW map shows relationship of M-36 to A-8 and M-8. P.15
- 1996 Hughes field witness' P.16

M-8, T1N, R4E, PUTNAM

2" DIAMETER PIPE IN WATER

- 359 DEG. 40.00' SET 1" PIPE WITH BRASS CAP.
- 273 DEG. 120.00' SET 1" PIPE WITH BRASS CAP.
- 046 DEG. 34.94' SET NAIL/TAG NW/S 26" POPLAR.
- 090 DEG. 24.63' SET NAIL/TAG N/S 8" TWIN ELM.
- 360 DEG. 120.96' TO A-8, T1N, R5E (A-8 IS 0.80' WEST OF M-8 / M-7 LINE).

1" PIPE 40' NORTH OF M-8

- 358 DEG. 80.96' TO A-8, T1N, R5E.
- 254 DEG. 124.14' SET 1" PIPE WITH BRASS CAP.
- 121 DEG. 30.28' SET NAIL NW/S 26" POPLAR.
- 075 DEG. 97.06' SET NAIL NW/S UTILITY POLE STUB.

1" PIPE 120' WEST OF M-8

- 045 DEG. 164.52' TO A-8, T1N, R5E.
- 074 DEG. 124.14' SET 1" IRON PIPE WITH BRASS CAP.
- 130 DEG. 4.39' SET NAIL/TAG N/S 4" POPLAR.
- 238 DEG. 20.80' SET NAIL/TAG N/S 6" POPLAR.

