

# SURVEY & REMONUMENTATION

FILED

APR 28 1995 LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Nov 16 2 01 PM '94

For corners in

LIVINGSTON  
(County)

**COMMISSION**  
Located In:

Corner Code =#

- |                                    |                         |             |       |
|------------------------------------|-------------------------|-------------|-------|
| 1. Public Land Survey              | T <u>1N</u> R <u>4E</u> | <u>M-11</u> |       |
|                                    | T _____ R _____         | _____       | _____ |
|                                    | T _____ R _____         | _____       | _____ |
|                                    | T _____ R _____         | _____       | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____       | _____ |
|                                    | S _____ T _____ R _____ | _____       | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____       | _____ |
|                                    | S _____ T _____ R _____ | _____       | _____ |

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI  
48843

L.S.C. #355m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

PUTNAM TWP.

I, DARRELL HUGHES, in a field survey on NOVEMBER 3, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1823 Joseph Wampler, Deputy Surveyor  
"Set post"  
No witnesses given


\*Additional historical information on back of sheet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner not found. Re-established 10.56 ft. South from A-11, T1N, R5E on A-11/M-13 line

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11, T1N, R4E, PUTNAM, established corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.  
180 DEG. 18.60' SET NAIL/TAG W/S 5" ASH.  
180 DEG. 186.98' FD. MONUMENT.  
360 DEG. 10.56' FD. 1/2" IRON ROD FOR A-1, T1N, R5E.  
238 DEG. 95.20' SET NAIL/TAG SE/S 24" WILLOW.  
260 DEG. 69.18' SET NAIL/TAG N/S 36" WILLOW.  
350 DEG. 24.77' SE COR. WOOD COTTAGE.



Signed by Darrell Hughes

Date 11-8-94

Surveyor's Michigan License No. 19834

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

PA. 345 1980, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 21 Sep 94 CO. REP [Signature]

PUTNAM TOWNSHIP, T1N, R4E

M-11, NORTHEAST CORNER SECTION 36

FIELD: 08-26-94

CORNER NOT FOUND. Initially we thought a found 1/2" smooth iron rod to be the corner. This 1/2" iron is A-11, the Northwest corner of Section 31, T1N, R5E, Hamburg Twp. Corner to be set 16 links (10.56') south of A-11 on A-11 / M-13 line.

- 1823 Corner first set by Joseph Wampler. P.7
- 1925 "Swarthout Cove" Plat by Grant Dunning P.8, calls for A-11, NW cor. Sec. 31, Hamburg.
- 1952 "Mumford Park No. 2" Plat by H.S. Hicks P.11, properly begins at A-11, does not show relationship to M-11. Shows monument southerly 204.26'. We measure from 1/2" iron rod to found monument at north shore of Portage Lake 197.5'+/-.
- 1963 "Shady Shores Colony No. 3" Plat by John Miller P. 10, shows M-11 and A-11 as common corner.
- 1971 Atwell-Hicks calls for monument at A-11. P.12, witness' check to the now found 1/2" iron.
- 1972 Oscar Boss finds monument A-11, ties vary from above. P.13.
- 1978 Pat Benton mislabels corner" SE cor. Sec. 25" and measures north 648.50' into "Swarthout Cove" record 649.00'. P.19.
- 1980 Garlock finds 1/2" iron rod and labels as A-11, witness 197.5' to fd. monument to south. Calculates S. 10.56' (GLO) for M-11 to be used in section line alinement to west. P.20-21.
- 1985-1986 Boss copies 1972 witness' onto new surveys. Found monument ?
- 1987 Hughes shows A-11 as north line of "Mumford Park No. 4" does not witness or show what physical evidence found. P.24.
- 1989 Boss finds 1/2" iron rod for A-11, new witness', P.27
- 1989 Garlock uses 1/2" iron (A-11) for survey north into "Swarthout Cove". 529.00' rec., 527.95' mea. P.28.
- 1991 Boss makes M-11 and A-1 a common corner. Uses A-11 for terminus of north line of Section 36. P.29