

FEB 24 1998

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1997 NOV 13 P 1:44

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

For corners in

LIVINGSTON  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 1 N R 4 E

I-11

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 19 94 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1823 Joseph Wampler, Deputy Surveyor  
Black Oak 20" South 01 degrees West 22 links  
White Oak 12" North 19 degrees West 109 links

\* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" iron pipe in asphalt pavement at intersection of Toma, Patterson Lake and Darwin Roads.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11, T1N, R4E, PUTNAM, replaced existing corner with 1 1/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 262 deg. 101.80' Set Nail / Tag N/S 36" Oak
- 235 deg. 36.00' Set Nail / Tag SE/S 24" Maple
- 039 deg. 46.24' Set Nail / Tag SE/S 12" Oak
- 040 deg. 56.73' Set Nail / Tag SE/S 24" Oak
- 299 deg. 83.95' CL 3" dia. Steel fence post
- 147 deg. 44.82' CL 4" dia. Steel fence post
- 358 deg. 7.13' Found bolt

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 9-28-94 CO. REP JED R.C.  
REVIEWED 3-19-97 (JED) BEFORE PEER GROUP.  
SUBMITTED 11-13-97 (JED)

Signed by Darrell Hughes

Date OCTOBER 6, 1997

Surveyor's Michigan License No. 19834

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11									●				
12		31		32		33		34		35		36	
13													

PUTNAM TWP.