

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Livingston</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>1N</u> R <u>5E</u>	<u>A-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

DEC 22 10 13 AM '93
 NANCY HAVILLARD
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843

FILED

L.S.C.# 90m
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Darrell D. Hughes, a field surveyor on December 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1819
 Maple 16" N86.5W 28 lks.
 Ash 14" N14E 58 lks.

*Additional historical information on back of sheet:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe with PK nail in center, 0.20' below asphalt pavement grade.

SURVEYOR
 REGISTERED PROFESSIONAL
 1993
 COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13, T1N, R5E, HAMBURG, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, set in cast iron road box and is accepted as a careful and faithful reestablishment of the position of the original corner.
 180 DEG. 33' TO CL "YANKEE LANE" EXTENDED FROM THE EAST.
 050 DEG. 37.54' SET NAIL/TAG S/S 36" MAPLE
 275 DEG. 57.24' SET NAIL/TAG S/S 10" LOCUST
 300 DEG. 42.90' SET NAIL/TAG N/S 8" ELM
 295 DEG. 58.60' SET NAIL/TAG N/S 14" LOCUST

Signed by Darrell D. Hughes Approved by Liv. Co. Peer Group: Nov. 03, 1993
 Date 12-21-93
 Surveyor's Michigan License No. 19834

PUTNAM TOWNSHIP, T1N, R4E

M-13, SOUTHEAST CORNER SECTION 36

FIELD 10-26-93

Found 1" pipe with PK nail in center, 0.20' below asphalt pavement grade, at centerline of McGregor Road, near point of curve for pavement. Act 74 No.795 ties not fd. newer ties by Boss fd. Did rough check to survey monumentation N, S and West.

Joseph Wampler set corner in 1819.

1903, Miles Bullock gave same witness for both Liv. Co. Townships.

1922-23, H.H. Atwell survey of Portage Lake Resort, shows corner common to 4 townships, with measures in 4 directions.

1932, shown at centerline of Public Highway and as Southeast corner of "Supervisor's Plat of Patrician Gardens", L.3, P.37, Liv.Co.Rec.

1974, Boss filed Act 74, 1" pipe, three ties not found.

1974, Atwell-Hicks survey shows corner common to townships and counties.

1987, Pat Benton, shows corner and PI relationship.

Corner is at blind curve in road, poor for instrument set-up due to safety. heavily traveled road.