

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in  
LIVINGSTON  
(County)

Located in: HAMBURG Corner Code #

9

1999 NOV 22 A 11:08

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

- 1. Public Land Survey T 1N R 5E C-9
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

LSC# 1113m

Register of Deeds Stamp and File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Bryan L. Boss, in a field survey on OCTOBER 20, 1999

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


- SET POST
- 10" BLACK OAK N34 1/2°W 20 LINKS
- 11" BLACK OAK S85°E 47 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- ESTABLISHED THE CORNER BY RETRACING THE 1952 AND 1954 GORDON/MUNSELL SURVEYS. AN IRON WAS FOUND 525' EAST OF THE CORNER THAT WAS CALLED OUT IN THESE SURVEYS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET 1 1/4"X36" PIPE WITH BRASS CAP STAMPED "LIVINGSTON COUNTY REMONUMENTATION CORNER"
- N35°E 24.76' SET REMON NAIL & TAG NW/SIDE 5" OAK
- N50°E 33.00' SET REMON NAIL & TAG S/SIDE 10" POPLAR
- S60°E 17.76' SET REMON NAIL & TAG E/SIDE 4" OAK
- S 70°W 20.38' SET REMON NAIL & TAG N/SIDE 6" OAK



P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY

PEER GROUP ON 9-15-99, CO. REP JED

Signed by [Signature]

Date NOV 11, 1999

Surveyor's Michigan License No. 29238