

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 NOV 22 A 11: 08

For corners in
LIVINGSTON
(County)

Located in: HAMBURG Corner Code #

9

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

- 1. Public Land Survey T 1N R 5E E-9
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

LSC# 1116m

Register of Deeds Stamp and File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Bryan L. Boss, in a field survey on NOVEMBER 3, 1999

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

SET POST
15" BLACK OAK S59°W 8 CHAINS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BRASS CAP STAMPED "LIVINGSTON COUNTY
REMONUMENTATION CORNER" ON TOP OF
EXISTING MONUMENT ALONG WITH A
CARSONITE MARKER

N30°E 44.67' SET REMON NAIL & TAG SE/SIDE 4" ELM
DUE EAST 81.59' SET REMON NAIL & TAG S/SIDE 6" ELM
S45°E 64.01' SET REMON NAIL & TAG SW/SIDE 8" ELM

N70°W 18.51' SET REMON NAIL & TAG NE/SIDE 2" WILLOW
DUE SOUTH 105' TO WATER'S EDGE OF BASS LAKE

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 8.18.99 CO. REP JED



Signed by [Signature] Date NOV 10, 1999
Surveyor's Michigan License No. 29238