

9  
 FILED  
 Alpha  
 #526

MAR 8 9 40 AM '96

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

NANCY HAVILAND  
 REGISTER OF DEEDS  
 LIVINGSTON COUNTY, MI  
 48843

For corners in

Livingston  
 (County)

Located In:

Corner Code //

- 1. Public Land Survey      T 1N R 5E      F-11
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section               S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous           S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec.         S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

L.S.C. #527m

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Bryan Boss, in a field survey on Jan. 29, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

North 1/4 corner Section 33 in lake. Post set in marsh East 1.45 chains (95.7 feet).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner was found to be inaccessible on 5-9-94 and 10-15-94. Corner to be set when ground is frozen by retracement of 1979 David C. Finney survey. Found David Finney R.L.S. #15536 iron at edge of river/lake. No evidence of any fence or occupation.

**SURVEY & REMONUMENTATION**

AUG 06 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Brass in 36" pipe at grade
- 36.47' North Nail/Tag West Side 4" Maple
- 8.86' N50°E Nail/Tag Northwest Side 3" Maple
- 18.94' East Nail/Tag North Side 2" Maple
- 5' ± West to Edge of Water

Signed by Bryan A. Boss

Date MARCH 4 1996

Surveyor's Michigan License No. 17022

SUMMARY F-11

NORTH 1/4 CORNER, SECTION 33, T1N-R5E, HAMBURG TOWNSHIP,  
LIVINGSTON COUNTY, MICHIGAN.

This Corner was found to be inaccessible on 5-9-94 and on 10-15-94 by two different Survey parties. We recommend reestablishing this Corner when ground is frozen and/or weather conditions permit.

In 1823 G.L.O. Survey Notes acknowledge the fact that the 1/4 Section corner is in Lake (see page 7 this Dossier). 1913 Grant Dunning Field Notes Page 8, also designate location of South 1/4 Corner to be in water.

In 1925, Clay Gordon platted "Cornwell Acres" Page 9 on South side of Huron River but does not indicate location of North 1/4 Corner of Section 33. 1941 Plat of "Indian Gardens" Page 10, denotes center of Section 28 as the point of Beginning but does not determine the location of the South 1/4 Corner of said section.

Conclusion: This corner will be set by retracement of David C. Finney Survey Pages 11 and 12. We find that the Southeast Corner of Parcel #6 of said Survey is the only point that makes reference to the North 1/4 Corner of Section 33, and should be accepted as found or set.

file:summf11

T1N-R5E  
F-11

Pg. 7