

FILED

DEC 28 4 17 PM '93

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI  
48843

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>1N</u> R <u>5E</u>	<u>L-11</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

L.S.C. #133m  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Bryan Boss, in a field survey on December 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Surveyed March 8, 1869 by M. W. Bullock  
W. Oak 14 in. Dia. N20 1/2°W 17 Lks.  
W. Oak 12 in. Dia. S73°E 35 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" Iron Pipe  
1 foot ± South of North Edge  
Strawberry Lake Road

SURVEY &  
REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1 1/4" x 18" Iron Pipe and Raised with  
1 1/4 x 6" pipe with Brass Cap Marked  
Livingston Co. Monument Corner Set in  
Monument Box

N20°W 43.10' SE Corner of House  
N55°E 55.80' Spike SE/Side Power Pole  
South 31.15' Spike NE/Side Power Pole  
N60°W 61.61' SW Corner of House


Approved by Livingston Co.  
Monumentation Peer Group  
on September 8, 1993

Signed by

*Bryan L. Boss*

Surveyor's Michigan License No.

29238



December 28, 1993