

**SURVEY &
REMONUMENTATION**

FEB 26 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in
LIVINGSTON
(County)

Located in: HAMBURG Corner Code #

9

2000 NOV 29 A 9:50

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC #1383m

Register of Deeds Stamp and File Number

- | | | | | | |
|---------------------------------------|---|----|---|----|-----|
| 1. Public Land Survey | T | 1N | R | 5E | F-5 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | R |
| | S | | T | | R |
| 3. Miscellaneous Property in Sec. | S | | T | | R |
| | S | | T | | R |
| 4. Lot No. _____, Recorded Plat _____ | | | | | |
| 5. Private Claims _____ | | | | | |

I, Bryan L. Boss, in a field survey on MARCH 7, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:


1823 BY S. SIBLEY, DEPUTY SURVEYOR
SET POST
W. OAK 13" N 01° W 55 LINKS
W. OAK 9" S 17° W 57 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1 1/4" X 3/8" PIPE AND BRASS CAP STAMPED
"LIVINGSTON COUNTY REMONUMENTATION
CORNER"
N 42° E 13.02' SET REMON NAIL/TAG W/SIDE 5"
LOCUST
N 58° E 22.14' FOUND CONCRETE MONUMENT
EAST 14.60' FOUND 1/2" IRON
S 53° E 23.40' SET REMON NAIL/TAG NE/SIDE 4"
LOCUST
S 30° W 5.82' SET REMON NAIL/TAG E/SIDE 4"
LOCUST



P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 3-1-2000 CO. REP JED

Signed by Bryan L. Boss

Date Sept. 22, 2000

Surveyor's Michigan License No. 29238