

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>16</u>	T. <u>1</u> N. R. <u>6</u> E.	<u>F-7, G-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>F-7 Found 3/8" iron with cap #13574 at fence corner.</p>	<p>G-7 Found 3/8" iron rod and large stone from witnesses supplied by Boss Engineering. S 88° W 26.50' Sp. in 20" Oak S 12° W 94.25' NE Cor. House S 28° W 39.70' NW Cor. House</p>
---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>F-7 Found 3/8" iron with cap #13574 at fence corner. S 52° E 8.88' Twin 4" Maple Spike & Tag S 58° E 22.76' 8" Cherry Spike & Tag N 70° E 37.69' 16" Sassafrass Spike & Tag N 40° E 31.35' 6" Sassafrass Spike & Tag N 14° E 39.41' 14" R. Oak Spike & Tag</p>	<p>G-7 Set 4" x 36" concrete monument with aluminum cap. S 84° W 5.71' 7" B. Cherry Spike & Tag N 53° E 5.90' 5" W. Oak Spike & Tag S 82° E 29.55' Triple 6", 8", 10" Cherry Spike & Tag S 20° E 13.09' 6" R. Oak Spike & Tag</p>
--	---

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE 12-19-79
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655