

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>4</u> T. <u>1</u> N. <u>6</u> E.	<u>Q.</u> , R. <u>6</u> E.	F-3, G-2
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- | | |
|--------------------------------|---|
| <p>F-3 Found 2" iron pipe.</p> | <p>G-2 Found 2" steel corner post of chain link fence 4' high which fit witnesses furnished by C&O Railroad. Oral testimony was obtained from local property owner and verified by local surveyor that the original corner was removed when the chain link fence was erected and the fence corner is now at that point.</p> |
|--------------------------------|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| <p>F-3 Set concrete monument with aluminum cap.
 South 5.54' 12" Oak Nail & Tag
 S 59° W 24.29' 7" Oak Nail & Tag
 N 19° E 4.47' 14" Cherry Nail & Tag
 S 89° E 41.96' 18" Oak Nail & Tag</p> | <p>G-2 Corner post of chain link fence 2" post 4' high
 S 78° E 17.62' 18" W. Oak Spike & Tag
 N 41° W 16.59' 18" R. Oak Spike & Tag
 S 88° W 18.83' 13" Hickory Spike & Tag
 South 246.0' N. Edge, N. Rail, RR Track</p> |
|---|---|

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE 12-19-79
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655