

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1999 NOV 22 A 11:10

For corners in

LIVINGSTON

(County)

Located in: GREEN OAK Corner Code #

9

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

- 1. Public Land Survey      T IN    R 6E    E-6  
                                  T \_\_\_\_\_ R \_\_\_\_\_  
                                  T \_\_\_\_\_ R \_\_\_\_\_  
                                  T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
   in Section               S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous           S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
   Property in Sec.         S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

LSC# 1139m

Register of Deeds Stamp and File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Bryan L. Boss, in a field survey on 10-12-99

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


SET POST  
3" RED OAK S. 54 1/2' E. 42L  
3" RED OAK N. 63 1/2' W. 33L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BRASS CAP STAMPED "LIVINGSTON COUNTY  
REMONUMENTATION CORNER" ON TOP OF  
EXISTING CONCRETE MONUMENT.  
S. 20°E 15.71' SET REMON. N/T W.SIDE 8"HICKORY  
DUE EAST 49.97' SET REMON N/T N.SIDE 24" OAK  
DUE WEST 40.80' SET REMON N/T S. SIDE 30" OAK  
N.30°W 30.03' SET REMON N/T W.SIDE 10" OAK



PA. 545 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 7-21-99, CO. REP JED

Signed by Bryan L. Boss

Date NOV. 3, 1999

Surveyor's Michigan License No. 29238