

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 NOV 22 A 11:10

For corners in

LIVINGSTON

(County)

Located in: GREEN OAK Corner Code #

9

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

1. Public Land Survey	T	IN	R	6E	E-7
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

LSC# 1140m

Register of Deeds Stamp and File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Bryan L. Boss, in a field survey on 10-12-99
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

SET POST
S.72°E 44 L 12" WHITE OAK
N. 3 1/2° W 23L 14" WHITE OAK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2" IRON PIPE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BRASS CAP STAMPED "LIVINGSTON COUNTY
REMONUMENTATION CORNER" ON EXISTING 2"
IRON PIPE
N70°W 37.18' SET REMON N/T S.SIDE 16" ELM
DUE NORTH 32.75' SET REMON N/T W.SIDE
24" OAK
S10°E 10.30' SET REMON N/T E.SIDE 26" OAK
S40W 48.90' SET REMON N/T N.W.SIDE 30" OAK



P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 7-21-99, CO. REP JED

Signed by Bryan L. Boss Date NOV. 9, 1999
Surveyor's Michigan License No. 29238