

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON

(County)

Located in: GREEN OAK Corner Code #

1. Public Land Survey	T	1N	R	6E	F-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Sec.	S		T		R
	S		T		R

9

NOV 22 A 11:11

HANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC# 1145m
Register of Deeds Stamp and File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Bryan L. Boss, in a field survey on 11-02-99
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


SET 1/4 POST AT AVERAGE DISTANCE
W. OAK 20" S46 1/2°W 56L
W. OAK 16" N48°E 54L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

ESTABLISHED CORNER FROM PREVIOUS SURVEY BY CLAY GORDON FROM POINTS FOUND 1050 FEET WEST AND FROM FOUND IRON ON THE NORTH R/W OF FAIRLANE RD (24.5' NORTH)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1 1/4" X30" PIPE WITH PLASTIC INSERT
CONNECTED TO 1 1/4" X 6" PIPE WITH BRASS
CAP STAMPED "LIVINGSTON COUNTY
REMONUMENTATION CORNER"
S80°W 52.10' SET REMON NAIL & TAG N/S 18"
HICKORY
NORTH 24.50' BOSS IRON FOUND
S80°E 59.15' SET REMON NAIL & TAG SW/S 12"
OAK
N40°W 33.25' SET REMON NAIL & TAG SW/S 24"
OAK



P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 9-1-99 CO. REP JEO

Signed by [Signature]
Surveyor's Michigan License No. 29238

Date NOV. 9, 1999