

MAR 17 2008

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1999 NOV 22 A 11:11

For corners in  
LIVINGSTON  
(County)

Located in: GREEN OAK Corner Code #

9

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

- 1. Public Land Survey      T IN    R 6E      G-7
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec.          S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

LSC# 1148m

Register of Deeds Stamp and File Number

I, Bryan L. Boss, in a field survey on 10-12-99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


SET POST  
N. 39°W. 71 L 13" BLACK OAK  
S. 24° W. 1.48 CH 13" WHITE OAK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND D.N.R. CONCRETE MONUMENT

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND D.N.R. CONCRETE MONUMENT  
DUE WEST 5.71' SET REMON NAIL & TAG S/S 14" CHERRY  
S20°E 13.03' SET REMON NAIL & TAG W/S 16" OAK  
N30°E 5.78' SET REMON NAIL & TAG W/S 8" OAK  
DUE EAST 29.48' SET REMON NAIL & TAG S/S 9" TRIPLE CHERRY



PA. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 7-21-99, CO. REP JED

Signed by [Signature] Date NOV 9, 1999  
Surveyor's Michigan License No. 29238