

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 NOV 22 A 11:12

For corners in
LIVINGSTON
(County)

Located in: GREEN OAK Corner Code #

9

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

- 1. Public Land Survey T 1N R 6E H-9
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

LSC# 1153m

Register of Deeds Stamp and File Number

I, Bryan L. Boss, in a field survey on 10-12-99
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
8												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


- SET 1/4 POST AT AVERAGE DISTANCE
- W. OAK 8" S09°E 45L
- B. OAK 13" N40°W 76L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON PIPE ON WEST AND SOUTH FENCE LINE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET 1 1/4" X 36" PIPE WITH BRASS CAP STAMPED
- "LIVINGSTON COUNTY REMONUMENTATION CORNER"
- S15°W 3.91' SET REMON NAIL & TAG E/S 24" HICKORY
- S45°W 43.41' SET REMON NAIL & TAG NW/S POWER POLE
- WEST 29.60' SET REMON NAIL & TAG N/S 30" HICKORY
- N10°E 29.64' SET REMON NAIL & TAG W/S TRIPLE CHERRY



P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 8.18.99 CO. REP JED

Signed by [Signature] Date NOV. 10, 1999
Surveyor's Michigan License No. 29238