

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 27 11 28 AM '93
NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

FILED

L.S.C.# 100m

Register of Deeds Stamp & File Number

For corners in

Livingston
(County)

Located In:

Corner Code ##

1. Public Land Survey

T 1N R 6E

I-11

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, H. Lawrence O'Donnell survey on December 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Survey in 1816 by Joseph Wampler
Set post cor to Secs 26, 27, 34 & 35

B. Oak 18 N58E 49 lks
W. Oak 14 S34W 26 lks

(Additional historical data on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Iron Pipe 4.2' South of centerline
of Nine Mile Road

3 Witnesses from LCS #849 verify this location

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1 1/4" x 42" breakway Iron Pipe with Brass Cap
in monument box

18" Oak N30°W 37.78' to nail with/flasher
26" Oak N40°E 40.48' to nail with/flasher
32" Maple S50°W 30.64' to nail with/flasher
30" Maple S30°W 26.24' to nail with/flasher



Signed by H. Lawrence O'Donnell Date December 23, 1993

Surveyor's Michigan License No. 28419

Approved by Livingston County Monumentation Peer Group November 6, 1993

Civil Engineering • Surveying
Planning • Environmental Services

A T W E L L - H I C K S , I N C .

540 Avis Drive
P.O. Box 2981
Ann Arbor, Michigan 48106
313 994 4000 • FAX: 313 994 1599

RESEARCH SUMMARY

I-11, NW Corner Section 35, T1N, R6E

Found 1/2" iron pipe at the location of the NW corner of Section 35.

Original GLO survey notes referenced set post corner to Sections 26, 27, 34 & 35 from which a black oak 18 in dia bears N58°E 49 lks
A white oak 14 in dia bears S34°W 26 lks

Old county survey records show Isaac Teller in 1886 recorded a 10" red cedar S25°E 55lks (36.7) and a 12" hard maple S63°W 103 lks (68.5). Also, Miles Bullock in 1895 calls a witness for Cedar 12 size 54.

Records of both C. Garlock and P. Benton show a 1" x 40" iron rod set (surveyor unknown) witnessed by:

SW corner N. Sluice abutment NE'LY 13.5
6" Twin Oak NW'LY 25.2
12" Maple SW'LY 30.6
Centerline road S'LY 4.8

Corner is referenced in 1973 survey by Tredinnick; 1974 PA 74 by Tredinnick; 1974 PA 74 by Jagow; 1975 survey by Kostecke.

A search of the area found no other irons. I conclude that this iron pipe marks the location of the NW corner section 35 T1N, R6E.



Mary A. Borkowski, RLA • William C. Henderson • Robert J. Jagow Jr., PE, PS • Robert G. Macomber, PE, PS
John L. Snyder, PE, PS • Allen R. Suggitt, PE • Richard G. Timmons, PE, PS