

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

9
FILED
 DEC 27 11 31 AM '93
 NANCY HAVILLAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843

For corners in Livingston (County) Located In: Corner Code ##

1. Public Land Survey	T <u>1N</u> R <u>6E</u>	<u>I-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

L.S.C.#99m
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, H. Lawrence O'Donnell in a field survey on December 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO survey in 1816 by Joseph Wampler
 set qr. sec post
 W. Oak 26 S01W 2.40 lks
 B. Oak 12 s49 1/2 E 2.07 lks
 (Additional historical data on back of sheet)

SURVEY &
 REMONUMENTATION
 1993
 COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron pipe as referenced in 1957 survey by atwell-Hicks.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1-1/4 x 36" Iron pipe with brass cap
 24" Maple East 12.83' to nail w/flasher
 18" Maple N70°W 26.84' to nail w/flasher
 12" ash N50°W 13.11' to nail w/flasher
 40" Maple N10°W 53.50' to nail w/flasher



Signed by H. Lawrence O'Donnell Date December 23, 1993
 Surveyor's Michigan License No. 28419

Civil Engineering • Surveying
Planning • Environmental Services

A T W E L L - H I C K S , I N C .

540 Avis Drive
P.O. Box 2981
Ann Arbor, Michigan 48106
313 994 4000 • FAX: 313 994 1599

RESEARCH SUMMARY

I-12, W 1/4 Corner Section 35, T1N, R6E

Found 1" Iron pipe in E-W fence line of the W 1/4 Corner location.

Original GLO survey notes reference set gr. section post in swamp form which a W. Oak 26 in dia bears S/W 2.40 lks and a B. Oak 12 in dia bears S49-1/2E 2.07 lks.

Earliest found reference to the corner was a March 5, 1957 survey by Atwell-Hicks, Inc. at which time a 1" Iron pipe was found.

Corner is referenced in a 1975 survey by Kostecke (which is not the actual corner); A 1975 survey by W.E. Co.; A 1979 survey by Roskelly & Jekabson; 1975 survey by W.E. Co.; 1976 survey Boss Engineering; 1982 survey by Boss Engineering; 1985 survey by Boss Engineering; 1992 survey by Boss Engineering.

A search of the county surveyor records did not provide any information on this corner. Records held by C. Garlock mad reference to a cedar stake in ditch marking the corner witnessed by E.m 12" S 49 1/2 E 121 lks., Isaac Teller County Surveyor in 1886.

A search of the area found no other irons. I conclude that this iron pipe marks the location of the W 1/4 corner Section 35, T1N, R6E.



Mary A. Borkowski, RLA • William C. Henderson • Robert J. Jagow Jr., PE, PS • Robert G. Macomber, PE, PS
John L. Snyder, PE, PS • Allen R. Suggitt, PE • Richard G. Timmons, PE, PS