

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843

DEC 27 11 24 AM '93

FILED

For corners in

Livingston <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>1N</u> R <u>6E</u>	<u>J-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

L.S.C.# 102m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, H. Lawrence O'Donnell survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GL0 survey November 1815 by Joseph Wampler
 Set qr. sec post
 Elm 12 N4E 20 lks
 Hickory 15 S8E 5 lks
 (Additional historical data on back of sheet)

SURVEY &
 REMONUMENTATION
 1993
 COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/2" iron pipe raised by 1" iron.
 Found iron pipe believed to be same as found in 1936 by W. Armstrong and in 1957 by Atwell-Hicks. Three of 1936 witnesses were found in 1957.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set brass cap in found 1-1/2" iron pipe
 0.7' below road surface.
 8" Birch N45° E 61.28' to nail w/ flasher
 14" Birch S33° W 40.81' to nail w/flasher
 12" Twin Walnut N76° W 118.65' to nail w/flasher
 Utility pole N30° W 49.68' to nail w/flasher



Signed by H. Lawrence O'Donnell Date December 22, 1993
 Surveyor's Michigan License No. 28419

Civil Engineering • Surveying
Planning • Environmental Services

A T W E L L - H I C K S , I N C .

540 Avis Drive
P.O. Box 2981
Ann Arbor, Michigan 48106
313 994 4000 • FAX: 313 994 1599

RESEARCH SUMMARY

J-13, S-1/4 Corner section 35, T1N, R6E

Found 1" iron rod at the S 1/4 corner location.

Original GLO survey notes refer to 1/4 corner post set 40 chains from SE corner section 35 witnessed by Elm 12" dia bearing N4°E 20 lks and a Hickory 15" dia bearing S8°E 5 lks.

Earliest found reference to the corner was 03-18-36 when Wm. Armstrong found an iron (size nor type described). A 1944 survey by Clay Gordon does not make reference to corner marker.

Corner is referenced in 1957 survey by Atwell-Hicks, Inc.; 1975 survey by W.E. Co.; (2) 1976 surveys by Boss Engineering; (2) 1977 surveys by Boss Engineering; 1979 PA 74 by Boss Engineering; 1980 survey by Boss Engineering; 1985 survey by Boss Engineering; and a 1992 survey by Kostecke.

A search of the county surveyor records and the historical survey records held by C. Garlock did not provide any information about this corner.

A search of the area found no other irons. I conclude that the iron found marks the S-1/4 corner location.



Mary A. Borkowski, RLA • William C. Henderson • Robert J. Jagow Jr., PE, PS • Robert G. Macomber, PE, PS
John L. Snyder, PE, PS • Allen R. Suggitt, PE • Richard G. Timmons, PE, PS