

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston \_\_\_\_\_ Located In: \_\_\_\_\_ Corner Code ## \_\_\_\_\_  
 (County)

1. Public Land Survey T 1N R 6E K-12  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Dec 27 11 14 AM '93  
 NANCY HAVILLAND  
 REGISTER OF DEEDS  
 LIVINGSTON COUNTY, MI  
 48643

FILED

L.S.C.# 104m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, H. Lawrence O'Donnell, filed survey on December 20, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO survey November 1815 by Joseph Wampler  
 Set gr. post  
 B. Oak 20 S10W 25 lks  
 B. Oak 7 N26E 34 lks

(Additional historical data on back of sheet)

SURVEY R  
 RECORDED  
 1993  
 COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe encased in concrete set in June 1957 as corner of Newman's Post Lane Farms Subdivision. Monument was recovered in May 1972 by Atwell-Hicks. A 3/4" pipe was set in December 1972 by C. Wilson as a replacement for monument but monument still exist.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set brass cap in top of concrete monument  
 24" Oak S70° W 33.88' nail w/ flasher  
 20" Cherry N05° E 12.52' nail w/ flasher  
 14" Elm S15° E 21.24' nail w/ flasher  
 12" Oak S10° W 15.10' nail w/ flasher



Signed by H. Lawrence O'Donnell Date December 22, 1993

Surveyor's Michigan License No. 28419  
 approved by Livingston County Monumentation Peer Group November 17, 1993

Civil Engineering • Surveying  
Planning • Environmental Services

# A T W E L L - H I C K S , I N C .

540 Avis Drive  
P.O. Box 2981  
Ann Arbor, Michigan 48106  
313 994 4000 • FAX: 313 994 1599

## RESEARCH SUMMARY

K-12 1/4 Corner Section's 35/36, T1N, R6E

Found 3/4" iron pipe with cap C.C.W. at the location of the 1/4 corner between Sections 35 & 36.

Original GLO notes refer to gr. post set from which

- a B. Oak 20 in dia bears S20°W 25lks.
- a B. Oak 7 in dia bears N26°E 34lks.

Earliest found reference to the corner was March 7, 1957 when a 3/4" iron pipe was set and later replaced with a monument for the plat of Newman's Post Lane Farms.

In May of 1972 Atwell-Hicks, Inc. found the monument. Later that same year Charles Wilson reset the corner with a 3/4" iron pipe from the plat and previous witnesses.

The corner has been used and referenced in surveys by Washtenaw Engineering 1973; W.E. Co survey in 1980; W.E. Co. survey in 1983; W.E. Co. survey in 1987 and a Atwell-Hicks, Inc. survey in 1992.

A search of the county surveyor records and the historical survey records held by C. Garlock, RLS, did not provide any information about this corner.

A search of the area found no other irons. I conclude that the iron found marks the 1/4 Corner between Sections 35 & 36.



Mary A. Borkowski, RLA • William C. Henderson • Robert J. Jagow Jr., PE, PS • Robert G. Macomber, PE, PS  
John L. Snyder, PE, PS • Allen R. Suggitt, PE • Richard G. Timmons, PE, PS