

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON  
(County)

Located In: Corner Code #

- |                                    |                         |            |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey              | T <u>2N</u> R <u>3E</u> | <u>B-9</u> |
|                                    | T _____ R _____         | _____      |
|                                    | T _____ R _____         | _____      |
|                                    | T _____ R _____         | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____      |
|                                    | S _____ T _____ R _____ | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____      |
|                                    | S _____ T _____ R _____ | _____      |

1996 NOV 14 P 1:20

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

L.S.C.#578m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DARRELL HUGHES, in a field survey on 11-11, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9		●											
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

IOSCO

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825  
Black Oak 20", North 27-1/2 degrees West, 24 links  
Black Oak 15", South 66-1/2 degrees West, 53 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No corner evidence found. Set corner GLO pro-rated distance on A-9/C-9 line.

\*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9, T2N, R3E, IOSCO, reestablished corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.  
039 DEG. 19.37' SET NAIL/TAG NW/S 6" OAK.  
084 DEG. 10.33' SET NAIL/TAG S/S 12" OAK.  
200 DEG. 5.01' SET NAIL/TAG E/S 6" OAK.  
259 DEG. 11.03' SET NAIL/TAG N/S 8" OAK.  
173 DEG. 13.04' SET 1/2" IRON ROD (TRAVERSE POINT).

Signed by Darrell Hughes  
Surveyor's Michigan License No. 19834

Date November 11, 1996

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 10-7-96 CO. REP JED

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1985

IOSCO TOWNSHIP, TOWN 2 NORTH, RANGE 3 EAST

B-9, NORTH 1/4 COR. SEC. 30 AND SOUTH 1/4 COR. SEC. 19.

FIELD: 9-30-1996 DARRELL D. HUGHES AND ASSOCIATES.

Corner not found, 12" corner post called for by Munsell in 1958 (P. 10) was not found nor witness trees. Many large trees in area, could not reconstruct Munsell ties. Munsell used this corner for measurements of the county drain East of this corner. There is no East/West occupation in this area, except for wood line to North. There is a N/S tree row and farm field division to the South with same owner East and West. I recommend, to the peer group, reconstructing B-9 from the 1996 Garlock survey (P.11A). Garlock pro-rated the GLO distances which check within a foot of pro-rating the 1861 Fairchild's distances, but did not need to set the corner for his survey.

- 1825 Sylvester Sibley, U.S. Deputy Surveyor, "West between 19 and 30, 40.00 chains, set 1/4 section post". P.7
- 1861 Ezra Fairchilds, county surveyor, surveys in Section 19. P.8
- 1875 Miles Bullock, county surveyor, surveys Section 30. P.9
- 1958 Lyle Munsell corner witnesses. P.10
- 1996 Charlie Garlock survey in Section 19. P.11