

9-

FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

1996 NOV 14 P 1:22

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48043

1. Public Land Survey

| | | | | |
|---|-----------|---|-----------|-------------|
| T | <u>2N</u> | R | <u>3E</u> | <u>B-13</u> |
| T | _____ | R | _____ | _____ |
| T | _____ | R | _____ | _____ |
| T | _____ | R | _____ | _____ |
| T | _____ | R | _____ | _____ |

2. Property Controlling in Section

| | | | | |
|---|-------|---|-------|-------|
| S | _____ | T | _____ | _____ |
| S | _____ | T | _____ | _____ |
| S | _____ | T | _____ | _____ |
| S | _____ | T | _____ | _____ |

3. Miscellaneous Property in Sec.

L. S. C. #598m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

IOSCO

I, DARRELL HUGHES, in a field survey on 11-6, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825
White Oak 22", North 70 degrees West, 90 links
White Oak 18", North 08 degrees East, 59 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Used old fence intersection for best evidence of location.


*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13, T2N, R3E, IOSCO, established corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.
287 DEG. 47.60' SET NAIL/TAG S/S 26" OAK.
322 DEG. 31.92' SET NAIL/TAG SW/S 17" OAK.
039 DEG. 23.76' SET NAIL/TAG NW/S 21" OAK. 5' ABOVE GRADE.
110 DEG. 13.25' SET NAIL/TAG S/S 9" CHERRY.

Signed by Darrell Hughes
Surveyor's Michigan License No. 19834

Date November 6, 1996



IOSCO TOWNSHIP, T2N, R3E

B-13, SOUTH 1/4 CORNER SECTION 31, ON THE SOUTH TOWNSHIP LINE.

FIELD: 9-30-1996, DARRELL D. HUGHES AND ASSOCIATES

No evidence found of any recent surveyors using or witnessing this corner. Found fence intersection at this location. No survey iron found. Fence wire North, East and West. A 36" Oak with rotted interior has fallen to the Northeast. Inside was evidence of wire fencing, 12" diameter circular wiring, wrapped around this tree when it was that size. A newer N/S fence exists 5' west of this older downed fence. I propose to the peer group the acceptance of this occupation for the location of B-13. I will set a remonumentation pipe in the hollowed rotted base of the then 12" tree. Poor for GPS. Measured 140' +/- West to B-1, 1/2" rerod, set by Carnahan in 1977.

- 1825 Sylvester Sibley, U.S. Deputy Surveyor, "West on the South boundary of Section 31, 40.00 chains, set quarter section post". P.7
- 1857 Abner B. Wood, Jr., county surveyor, uses "post" for survey in the Southeast 1/4 of Section 31. P.8
- 1977 Whitney Carnahan establishes North line of Section 6, T1N, R3E, apparently did not find or witness this corner. Also, apparently set B-1 on line with A-1 and C-1 at pro-rated distance. B-1 falls 6' South of found E/W fence.