

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

9-
FILED

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>3E</u>	<u>C-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1996 NOV 14 P 1:20

NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI.
 40843

L.S.C.#576m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, DARRELL HUGHES, in a field survey on 1-5, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

IOSCO

A. Description of original monument and accessories and/or subsequent restoration:
 GLO: 1825
 White Oak 18", North 87 degrees West, 10 links
 White Oak 9", South 33-1/2 degrees East, 22 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2" iron pipe set by C.C. Wilson in 1972.

*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10, T2N, R3E, IOSCO, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful perpetuation of the position of the original corner.
 095 DEG. 42.65' SET NAIL/TAG NW/S 36" TWIN MAPLE.
 274 DEG. 55.37' SET NAIL/TAG S/S 22" MAPLE.
 003 DEG. 42.73' SET NAIL/TAG E/S 22" CHERRY.
 197 DEG. 47.97' SET NAIL/TAG E/S 36" QUAD. MAPLE.

Signed by Darrell Hughes
 Surveyor's Michigan License No. 19834

Date November 5, 1996

IOSCO TOWNSHIP, TOWN 2 NORTH, RANGE 3 EAST

C-10, EAST 1/4 COR. SEC. 30 AND WEST 1/4 COR. SEC. 29.

FIELD: 9-30-1996 DARRELL D. HUGHES AND ASSOCIATES.

Found 1/2" iron pipe at base of 12" Ash in low Maple swamp area. This pipe was set by Charles Wilson in 1972. Downed fence wire runs North, South, East and West from this pipe. No evidence of a fence corner post. The Act 74 witnesses of Wilson agree to centerline of trees stated. No nails found, except for one with tag No. 19009 (William Worth, Grass Lake). Called Mr. Worth for copy of survey. Have not received it. In 1979, Austin Williams used this pipe for a survey in the SE 1/4 Sec. 30. I recommend, to the peer group, the acceptance of this pipe for the location of C-10. Poor for GPS.

- 1825 Sylvester Sibley, U.S. Deputy Surveyor, "North between 29 and 30, 40.00 chains, set 1/4 section post". P.7
- 1840 Amos Adams, county surveyor, surveys in SE 1/4 Sec. 30. P.8
- 1875 Miles Bullock, county surveyor, surveys Sec. 29. P.9
- 1875 Miles Bullock, surveys Section 30.. P.10
- 1972 Charles Wilson, sets this pipe in survey and files Act 74. P.11
- 1974 Oscar Boss, shows corner in survey, no witnesses. P.12
- 1979 Austin Williams, uses corner in survey, copies Wilson witnesses. P.13
- 1996 Witness list. P.14