

9-
FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------------------------|-------------|
| 1. Public Land Survey | T <u>2N</u> R <u>3E</u> | <u>C-12</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

1996 NOV 14 P 1:20

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C.#580m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DARRELL HUGHES, in a field survey on 11-6, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	● 32	33	34	35	36						
13												

IOSCO

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825
White Oak 25", South 06 degrees East, 92 links
White Oak 30", North 38 degrees West, 226 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 3/4" iron pipe at fence intersection in rock pile.

*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12, T2N, R3E, IOSCO, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful perpetuation of the position of the original corner.
004 DEG. 50.10' SET NAIL/TAG E/S 18" WHITE OAK.
127 DEG. 6.22' SET NAIL/TAG S/S 32" RED OAK.
195 DEG. 41.74' SET NAIL/TAG W/S 20" RED OAK.
248 DEG. 22.22' SET NAIL/TAG SE/S 29" WHITE OAK.
176 DEG. 15.06' FD. 3/4" IRON PIPE

Signed by Darrell Hughes
Surveyor's Michigan License No. 19834

Date November 6, 1996

IOSCO TOWNSHIP, T2N, R3E

C-12, WEST 1/4 CORNER SECTION 32 AND EAST 1/4 CORNER SECTION 31.

FIELD: 9-30-1996 DARRELL D. HUGHES AND ASSOCIATES

Found 3/4" iron pipe, at grade, set by Robert Jagow in 1973, witnesses check. Pipe set on line and at 1/2 distance between C-13 (set at occupation) and C-11 (found 1/2" iron pipe). Also found an old 3/4" iron pipe, no cap, 0.3' above grade, 356 Degrees 15.06' from the Jagow pipe, at the base of a fallen, wire wrapped, wooden, fence corner post, surrounded by rocks, downed fence wires, N, S, E and W. No witness nails found in any of the surrounding prominent trees. I recommend, to the peer group, the acceptance of the iron pipe at the occupied fence intersection, for the location of C-12. In wooded area, poor for GPS.

- 1825 Sylvester Sibley, U.S. Deputy Surveyor, "North between Sections 31 and 31, 40.00 chains, set 1/4 section post". P.7
- 1840 Amos Adams, county surveyor, finds "post" in survey of the Northeast 1/4 of Section 31. P.8
- 1857 Abner B. Wood, Jr., county surveyor, finds "post" in survey of the N 1/2 of the Southeast 1/4 of Section 31. P.9
- 1973 Robert Jagow, "finds no evidence of corner" sets 3/4" iron pipe at 1/2 distance and on line with C-11 and C-13 and files Act 74. P.10-12
- 1996 Witness list. P.13
- 1996 Ray Kostecke survey shows corner, no witnesses, his measures, North, to C-11 agree with Jagow pipe. P.14