

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

9-
FILED

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>3E</u>	<u>C-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

1996 NOV 14 P 1:20

NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI.
 48843

L.S.C. #58 Im
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, DARRELL HUGHES, in a field survey on 11-5, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

IOSCO

A. Description of original monument and accessories and/or subsequent restoration:
 GLO: 1825
 Black Oak 12", North 08 degrees East, 373 links
 Black Oak 8", North 49-1/2 degrees West, 300 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 3/4" iron pipe set by Jagow in 1973.

*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13, T2N, R3E, IOSCO, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful perpetuation of the position of the original corner.
 189 DEG. 27.46' SET NAIL/TAG E/S 10" TRIPLE MAPLE.
 083 DEG. 32.96' SET NAIL/TAG N/S 8" MAPLE.
 015 DEG. 31.43' SET NAIL/TAG W/S 15" MAPLE.
 323 DEG. 25.07' SET NAIL/TAG NE/S 8" TWIN MAPLE.

Signed by *Darrell Hughes*
 Surveyor's Michigan License No. 19834

Date November 5, 1996

MICHIGAN
 DARRELL HUGHES

IOSCO TOWNSHIP, T2N, R3E

C-13, SOUTHWEST COR. SEC.32 & SOUTHEAST COR. SEC. 31, ON THE SOUTH TOWNSHIP LINE.

FIELD: 9-27-96 DARRELL D. HUGHES AND ASSOCIATES.

Found 3/4" iron pipe on South side wood fence post corner. Wires run North, East and West. Measures 145.30 feet to C-1, T1N, R3E. This pipe was set by Atwell-Hicks in 1973. Carnahan (1977) and Hughes (1990) have used this pipe in surveys. I recommend to the peer group the acceptance of this pipe for the location of C-13. Poor for GPS.

- 1825 Sylvester Sibley, U.S. Deputy Surveyor, "West on the South boundary of Section 32, 80.00 chains, set post common to sections 31 and 32". P.7
- 1973 Robert Jagow sets 3/4" iron pipe in performance of survey. P.8-10 (see Act 74, page 9 on how set, par.B).
- 1977 Carnahan performs survey in Sec. 6, T1N, R3E, witness' this corner but shows no relationship to C-1 or the South line of Section 31, T2N, R3E. P.11-12
- 1990 Hughes finds 3/4" iron pipe and uses in survey to set D-1, T1N, R3E. Files Act 74. P.13-14
- 1996 Witness comparison list. P.15