

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

9.

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>3E</u>	<u>D-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

1996 NOV 14 P 1:27

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #600m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DARRELL HUGHES, in a field survey on 11-6, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		19		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

IOSCO

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825
White Oak 9", North 21 degrees West, 112 links
Black Oak 32", North 08 degrees East, 118 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod set by Garlock in 1975.

*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13, T2N, R3E, IOSCO, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful perpetuation of the position of the original corner.
127 DEG. 20.21' SET NAIL/TAG N/S 17" MAPLE.
348 DEG. 71.21' SET NAIL/TAG E/S 32" CHESTNUT.
273 DEG. 94.40' SET NAIL/TAG N/S 8" ELM.
234 DEG. 66.23' SET NAIL/TAG E/S 10" ELM.

Signed by Darrell Hughes
Surveyor's Michigan License No. 19834

Date November 6, 1996

IOSCO TOWNSHIP, T2N, R3E

D-13, SOUTH 1/4 CORNER SECTION 32, ON SOUTH TOWNSHIP LINE.

FIELD: 9-27-96 DARRELL D. HUGHES AND ASSOCIATES

Found 1/2" rerod (no cap), 6' East of physical centerline Dutton Road (gravel), on eyed fence lines East and West of Dutton Road. 0.8' below grade. Marginal for GPS. This rerod was set by Garlock in 1975, "Set from previous deeds and prorated distances N, S, E and W." Act 74. I recommend to the peer group the acceptance of this found iron for the location of D-13.

1825 Sylvester Sibley, Deputy U.S. Surveyor, "West on the South boundary of Sec. 32, 40.00 chains, set 1/4 section post". P.7

1975 Garlock sets 1/2" iron rod in performance of a survey and files an Act 74. P.8-9

1990 Hughes finds Garlock iron, uses in survey and files Act 74. P.10-11

1994 Hughes uses same iron in survey, new witnesses. P.12

1996 Witness list. P.13