

FILED

OCT 16 11 43 AM '95

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

corners in

LIVINGSTON (County)	Located In:	Corner Code #
Public Land Survey	T <u>2N</u> R <u>3E</u>	<u>E-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
Property Controlling	S ___ T ___ R ___	_____
in Section	S ___ T ___ R ___	_____
Miscellaneous	S ___ T ___ R ___	_____
Property in Sec.	S ___ T ___ R ___	_____

L.S.C.# 486m

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

IOSCO TWP.

DARRELL HUGHES, in a field survey on FEB. 22
JANUARY 11, 19 95,
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
rent manual of survey instructions of the United States Department of the Interior, Bureau of Land
management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

Description of original monument and accessories and/or subsequent restoration:

GLO: 1825, Sylvester Sibley, Deputy Surveyor
"Set post in swamp"
Tamarack 14", South 62 degrees East, 185 links
Tamarack 16", North 33-1/2 degrees East, 194 links

SURVEY &
REMONUMENTATION


NOV 27 1995

Description of corner evidence found and/or method applied in restoring or reestablishing corner: **COMMISSION**
Found 1 inch iron pipe.

*Additional descriptions and historical information on back of this sheet.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11, T2N, R3E, IOSCO, replaced existing corner with 1-1/4" X 36" iron
pipe, affixed with 2" dia. brass cap, stamped "Livingston Co.
Monumentation Corner, P.S. 19834, and is accepted as a careful and
faithful reestablishment of the position of the original corner.
004 DEG. 19.79' SET NAIL/TAG W/S RR TIE CORNER FENCE POST.
081 DEG. 98.46' SET NAIL/TAG S/S WOOD FENCE POST.
120 DEG. 87.53' SET NAIL/TAG N/S 14" ELM.
188 DEG. 38.48' SET NAIL/TAG W/S 12" ELM.
224 DEG. 39.87' SET NAIL/TAG NW/S 5" POPLAR.



signed by Darrell Hughes Date October 5, 1995
Surveyor's Michigan License No. 19834

IOSCO TOWNSHIP, T2N, R3E

E-11, CORNER COMMON TO SECTIONS 28, 29, 32 AND 33

FIELD, JANUARY 11, 1995 Darrell D. Hughes and Associates

Found 1" iron pipe in centerline Roberts Road at N/S fence line to North. Pipe 0.2' below gravel road grade.
For GPS- trees South and Northwest, open Northeast.

1825 Sylvester Sibley, U.S. Deputy Surveyor - North between 32 and 33, 80.00 chains set post in swamp. (P.7,7a)

1877 Emerson Grant, county surveyor, shows witness' to Tamaracks. (P.8-9)

1972 Charles Wilson sets 1/2" iron pipe and files Act 74. (P.10-11) E11 to F11 2649.23', E11 to D11 2635.56'

1991 Darrell Hughes finds 1/2" iron pipe (bent) replaces with 1" iron pipe. sets new witness' (P.13-13A) E11 to F11 2648.04'

1992 Norman Kaipio #25851, finds 1/2" iron pipe and copies Wilson's witness'. E11 to F11 2648.08'

1993 Hughes retraces parcel 13 of Wilson (1972) and divides. E11 to D11 2635.33'. (P15)

1995 Hughes witness' for Liv. Co. remonumentation. (P.16) E11 to F11 2648.13'