

MAR 17 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in SECTION

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2</u> N R <u>3</u> E	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

α'

1999 NOV 22 A 10: 06

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

ISC #1063m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28	●	27		26		25	
11													
12		31		32		33		34		35		36	
13													

IOSCO TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
WHITE OAK 18" N48E 62 LINKS
WHITE OAK 15" S73W 160 LINKS

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REROD #17022, 0.6' BELOW GRAVEL ROAD GRADE NEAR
EAST EDGE GRAVEL ROAD. OCCUPATION TO EAST AND WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10, T2N, R3E, IOSCO, set corner with 3/4" x 36" iron pipe, affixed with 2" dia. Brass disk.
Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 098 DEGREES 20.84' SET NAIL/TAG SW/S 26" OAK.
- 175 DEGREES 65.50' SET NAIL/TAG NW/W 14" HICKORY.
- 237 DEGREES 39.67' SET NAIL/TAG SE/S 9" HICKORY
- 338 DEGREES 42.50' SET NAIL/TAG E/S 15" OAK.

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 2-3-99, CO. REP JED

Signed by Darrell Hughes
Surveyor's Michigan License No. 19834

Date NOVEMBER 3, 1999