

SURVEY & REMONUMENTATION

FILED

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

NOV 16 1 59 PM '94

For corners in **COMMISSION**

LIVINGSTON
(County)

Located In:

Corner Code #

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

- 1. Public Land Survey T 2N R 3E G-13
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

L.S.C. #327m

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

DARRELL HUGHES, in a field survey on NOVEMBER 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
Tamarack 11" North 53 degrees West 280 links
White Oak 11" North 18½ degrees East 62 links

*Additional historical information on back of sheet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 3/4" pipe in centerline of E/W ditch Cap #33971

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13, T2N, R3E, IOSCO, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.
270 DEG. 185.08' FD. 3/4" IRON PIPE 33971 FOR G-1, T1N, R3E.
276 DEG. 144.91' SET PK/TAG TOP CENTER E.END 6' CMP.
103 DEG. 45.82' SET NAIL/TAG N/S 20" STUMP.
282 DEG. 60.12' SET NAIL/TAG N/S 5" TREE.



Signed by Darrell Hughes

Date November 2, 1994

Surveyor's Michigan License No. 19834

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

PA. 345 1890, APPROVED BY LIVINGSTON COUNTY

PEER GROUP ON 3 Aug 94 CO. REP R. W. [Signature]

IOSCO TOWNSHIP, T2N,R3E

G-13, SOUTHWEST 1/4 SECTION 34 & SOUTHEAST 1/4 SECTION 33

FIELD 2-22-1994 D.D.HUGHES AND ASSOCIATES, FOWLerville.

Found 3/4" pipe in centerline E/W ditch with Barnwell cap, originally set by Benton 1982 (P.10). Distance West to G-1 Unadilla 185.08', (GLO) 190.08' P.7A. 1/2 mile measures to North 2629.91' Benton, 2629.78' Hughes; to East 2647.41' Hughes, 2647.36' Barnwell. Good for GPS.

1825 Sylvester Sibley, U.S. Deputy Surveyor, set post at 80 chains from East. P.7

1872 Miles Bullock, divides all of Section 34. P.8

1953 Clay Gordon shows corner on survey. 183' West to G-1 Unadilla. P.9

1982 Benton sets 3/4" pipe, 4' long, in ditch centerline. P.10

1993 Barnwell finds pipe with cap No 33971, P.11A.

1994 Hughes surveys P.12-13.