

MAR 17 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in SECTION

LIVINGSTON  
(County)

Located In:

Corner Code #

- |                                    |  |            |
|------------------------------------|--|------------|
| 1. Public Land Survey              | T <u>2</u> N R <u>3</u> E              | <u>H-9</u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u> |
| 2. Property Controlling in Section | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
| 3. Miscellaneous Property in Sec.  | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u> |

o

1999 NOV 22 A 10:07

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LSC #1064m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9								●					
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

IOSCO TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor  
WHITE OAK 8" N3E 56 LINKS  
BLACK OAK 14" S77½W 30 LINKS

\* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/4" REROD IN DEPRESSION SURROUNDED BY STONES, FORMER WOOD FENCE POST, 2' BELOW GRADE. WIRE TO NORTH, SOUTH, EAST AND WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9, T2N, R3E, IOSCO, set corner with 3/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 011 DEGREES 21.70' SET NAIL/TAG W/S TWIN 18" OAK.
- 093 DEGREES 21.60' SET NAIL/TAG SW/S 16" CHERRY.
- 183 DEGREES 20.96 SET NAIL/TAG E/S 18" ELM.
- 265 DEGREES 48.66' SET NAIL/TAG S/S 40" OAK.

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 2-3-99, CO. REP JED

Signed by Darrell Hughes

Date NOVEMBER 3, 1999

Surveyor's Michigan License No. 19834