

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIVINGSTON
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 2 N R 3 E I-9
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
BLACK OAK 11" S32½E 52 LINKS
WHITE OAK 24" N75W 32 LINKS

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND ½" IRON ROD NEAR CENTER LINE N/S ASPHALT PAVEMENT, AT GRADE.
OCCUPATION TO WEST AND EAST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9, T2N, R3E, IOSCO, set corner with ¾" x 36" iron pipe, affixed with 2" dia. Brass disk.
Disk stamped "Livingston Co. Monumentation Corner, 19834" in road box and is accepted as a careful and faithful reestablishment of the position of the original corner.

097 DEGREES 36.21' 21/2" ANGLE IRON FENCE CORNER POST, 1' ABOVE GRADE.
130 DEGREES 40.36' SET NAIL/TAG SW/S 48" OAK.
220 DEGREES 55.54' SET NAIL/TAG NW/S 8" PINE.
340 DEGREES 112.05' SET NAIL /TAG SW/S 12" PINE.

FILED

1999 NOV 22 A 10:07

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

I.S.C #1065m

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3			2	1
3													
4	7			8			9		10			11	12
5													
6	13			17			16		15			14	13
7													
8	19			20			21		22			23	24
9													
10	30			29			28		27			26	25
11													
12	31			32			33		34			35	36
13													

IOSCO TWP.

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 2-3-99, CO. REP JED

Signed by [Signature]

Date NOVEMBER 3, 1999

Surveyor's Michigan License No. 19834